

1 When recorded, return to:
2 Paradise Valley Town Attorney
3 6401 East Lincoln Drive
4 Paradise Valley, Arizona 85253
5
6
7

8 **ORDINANCE NUMBER 2016-13**
9

10 **AN ORDINANCE OF THE TOWN OF PARADISE VALLEY,**
11 **ARIZONA, AMENDING THE ZONING ORDINANCE**
12 **ARTICLE II, DEFINITIONS, AND ARTICLE IX, CLUSTER**
13 **PLAN DISTRICT; PROVIDING FOR SEVERABILITY; AND**
14 **PROVIDING FOR AN EFFECTIVE DATE.**
15

16 WHEREAS, in accordance with Article II, Sections 1 and 2, constitution of Arizona, the
17 Town Council has considered the individual property rights and personal liberties of the
18 residents of the Town before adopting this ordinance.

19
20 **NOW, THEREFORE, BE IT ORDAINED BY THE MAYOR AND TOWN COUNCIL OF**
21 **THE TOWN OF PARADISE VALLEY, ARIZONA THAT:**
22

23 Section 1. Article II, Definitions, Section 201, is hereby amended as follows (with deletions
24 shown as ~~strikethroughs~~ and additions shown in **bold type**):
25

26 Cluster Plan (CP) District: A development approach that may be used in the R-43 or R-35
27 Cluster Plan zoning district that retains the same house per acre ratio as the R-43 or R-35, zoning
28 districts permitting reduced lot sizes in order to allow undeveloped land to be preserved as open
29 space. This approach may be utilized to preserve natural features-~~or~~, to provide greater than
30 normal setbacks from heavily traveled thoroughfares, **or to allow flexibility in the development**
31 **of parcels on the perimeter of the Town.**
32

Section 2. Article IX, Cluster Plan District, is hereby amended as follows (with deletions shown as ~~strike throughs~~ and additions shown in **bold type**):

Article IX CLUSTER PLAN DISTRICT

Section 901. Purpose:

The purpose of this section is to provide a zoning district as an alternate zoning to R-43 and R-35 single family residential districts, and thereby making provisions for variations in lot sizes within tracts of eight (8) acres or more while maintaining the necessary requirements for open space within each tract as a whole, in order to preserve the natural beauty of the Town of Paradise Valley:

1. A cluster plan may be approved only for the following reasons:

- (a) To preserve areas which have natural features of scenic beauty of significance to the general public.
- (b) To provide greater than normal residential setbacks from heavily traveled thoroughfares without reducing the number of residential lots that might otherwise be created within the provisions of this Ordinance.
- (c) **To allow flexibility for development of parcels on the perimeter of the Town which lack physical access to Town streets and which meet the criteria set forth in the first paragraph of Section 912.**

1 Nothing in this article shall confer upon any applicant a right or claim to have a cluster plan
2 approved as a matter of course. Such approval shall vest in the sound discretion of the Town
3 Planning Commission (hereinafter called Commission), and of the Town Council at a public
4 hearing with due regard to the public safety, health, morals, and welfare of the Town.

5
6 Section 902. Variation in Lot Sizes:

7 The owner of a tract of land in a R-43 or R-35 Residential Zoning District may, upon obtaining
8 the approval of a cluster plan in accordance with the provisions of this Article, vary the lot sizes
9 within the tract of land from those required by the applicable zoning district. Applications for
10 the approval of such cluster plans shall be made in accordance with the provisions of Section
11 908.

12
13 Section 903. Maximum Number of Lots:

14 The maximum number of lots within a tract of land that may be authorized under this Article
15 shall be computed by dividing the “gross acreage” as that term is hereinafter defined, by the
16 maximum lot area requirement of the single family dwelling district in which the lot is located.

17 The term “gross acreage” as used herein, shall include the land within the exterior boundaries of
18 a tract, less the following:

- 19
20 1. The area comprising easements of record for public utilities facilities such as electric
21 transmission lines, sewer lines, and water mains, except in those cases where the owner
22 shall satisfy the Commission that the existence of the easement does not prevent the use
23 of the area comprising the easement for development;

2. An area representing probable street rights of way if the tract were to be developed as a subdivision without regard to the provisions of this Article.

Gross acreage shall not include any portion of the tract, which the owner does not propose to alienate, either as a lot sold to a purchaser, or as common lands conveyed to trustees. The Commission may by rule adopt regulations calculated to insure compliance by the owner with the provisions of the proposed cluster plan pertaining to conveyance of lots and common lands.

Section 904. Inclusion of Common Lands.

Lands shall be set aside from the remainder of the tract for common use by all of the owners of the residential lots, in accordance with the provisions of this section, and such common lands shall be included in the gross acreage for purposes of computing the maximum number of lots authorized under this Article. Except in the case of bridle paths designated as such in the cluster plan, no animals other than domestic pets shall be permitted on common lands. Common lands shall be set aside only for the following uses:

1. Private recreational facilities, such as swimming pools, which are limited to the use of the owners or occupants of the lots located within the tract, or their guests;
2. Parks and parkway areas, and areas which have natural features of scenic beauty worthy of preservation;
3. Bridle paths, golf courses, or hiking trails for the use of the owners of the said lots, or for the use of the general public.

1 Section 905. Conveyance of Common Lands:

2 All common land designated in the plan as such, or whose acreage shall be utilized in the
3 determination of the maximum number of lots that are authorized, shall be conveyed in fee
4 simple by warranty deed from the owner to trustees. A proposed form of trust indenture shall be
5 included in each application for approval of a cluster plan. Such trust indenture shall provide,
6 among other things, that the trustee shall hold title for the sole benefit, use, and enjoyment of the
7 lot owners, present and future, of said subdivision for a term of years certain, which term shall
8 not be less than twenty (20) years. The trust indenture shall further provide that upon the
9 expiration of the said term of years, or upon the cessation of the subdivision, fee simple title to
10 the said land shall be vested in said lot owners as tenants in common. In addition, there shall be
11 included in the plan a proposed form of covenant for inclusion in the deeds to the lots, which
12 covenant shall provide a suitable means for the maintenance and upkeep of the common lands,
13 and shall obligate the lot owner and his successors for a proportionate share of the cost of such
14 upkeep and maintenance. By including the form of such a covenant in the plan, the owner
15 represents and warrants that such a covenant will be included in the original deed to each lot in
16 such a manner as to run with the land and bind succeeding lot owners. The warranty deeds and
17 trust indentures shall be attached as exhibits to the cluster plan together with the opinion of an
18 attorney admitted to practice in Arizona, addressed to the Commission, to the effect that the said
19 deeds and trust indentures comply in form and in substance with the provisions of this
20 Ordinance. The indentures shall be recorded in the office of the Maricopa County Recorder
21 simultaneously with the recording of the final plat of the subdivision, as provided in the
22 subdivision regulations of the Town. Each deed from the owner to a purchaser of a lot, which is
23 subject to the cluster plan, shall include the covenant.

1 Section 906. Minimum Reduced Size of lots:

2 No lot developed under the provisions of this section shall be reduced in area or frontage below
3 the minimum standards set forth in the following table **except as set forth in Section 912:**

	Minimum Reduced	Minimum Reduced
<u>Density</u>	<u>Area</u>	<u>Frontage</u>
7 R-43 (one acre)	20,000 sq. ft.	120 feet
8 R-35 (35,000 sq. ft.)	20,000 sq. ft.	100 feet

10 Section 907. Maintenance of Average Lot Size:

11 Lots developed under this Article may be reduced in area below the minimum lot size required
12 by the residential district zone in which the subdivision is located (but not below the minimum
13 standards set forth in the preceding paragraph) provided that the gross acreage, when divided by
14 the number of lots created, shall equal the minimum lot size required by the applicable district.

16 Section 908. Cluster Plan Procedure:

17 The owner of any tract of land comprising an area of not less than eight (8) acres may submit to
18 the Commission a re-zoning request for a cluster plan for the use and development of all of the
19 said tract of land for residential purposes; the plan shall include all information which the
20 Commission may by rule require, and shall include a request that the entire tract in question be
21 zoned "CP." No cluster plan shall be submitted to the Commission for its approval until a
22 preliminary plat of the tract, which is the subject of the cluster plan, has likewise been submitted,

1 as required by the subdivision regulations of the Town. The preliminary plat shall show in detail
2 each variation from lot size otherwise required which is sought under the proposed cluster plan.
3

4 Every cluster plan submitted under this section shall be considered by the Commission at a
5 public hearing. Such public hearing shall be held only after one publication of a public notice of
6 the time, place and date of such hearing is given in a newspaper of general circulation in the
7 Town of Paradise Valley at least fifteen (15) days prior to such hearing, and after there has been
8 posted on the affected property at least fifteen (15) days prior to the said hearing a notice of the
9 hearing.
10

11 The Commission shall, after such public hearing, submit to the Town Council its
12 recommendation of approval or disapproval of the cluster plan. Approval of a cluster plan shall
13 not be recommended by the Commission until it shall have also approved the preliminary plat for
14 subdivision of the land, which is the subject of the cluster plan in accordance with the
15 subdivision regulations of the Town.
16

17 Upon submission of the Commission's recommendation, the Town Council shall arrange to hold
18 its public hearing to consider whether the cluster plan shall be approved. Like notice for the
19 hearing of the plan before the Town Council shall be given as is the case of the hearing of the
20 plan before the Commission.
21

1 Section 909. Other Provisions Applicable.

2 If the Town Council shall approve the cluster plan, development in conformity with the plan may
3 be undertaken, even though the location of the buildings to be erected in the area, and the yards
4 and open spaces contemplated by the plan, depart in respect herein above authorized from the
5 district regulations of the district in which the tract is located. Such development of the tract
6 shall be subject to the applicable provisions of the Town subdivision regulations pertaining to the
7 installation of required improvements and submission of the final plat. In the event that the
8 approval of the preliminary plat becomes void by reason of the lapse of time under the provisions
9 of the Town subdivision regulations, the approval of the cluster plan by the Town Council shall
10 likewise become void.

11
12 Land use within any tract zoned "CP" shall be subject to all other applicable provisions of this
13 Ordinance, and of other ordinances of the Town, except as herein expressly otherwise provided.
14 Notwithstanding the fact that a cluster plan may have been approved for lots located in either and
15 R-43 or an R-35 district, which plan permits one or more of said lots to be varied below the
16 minimum area regulation applicable to the district in which they are located; (a) no guest house
17 shall be permitted on any such lot which does not meet the minimum area regulations applicable
18 to the district in which it is located, without regard to the provisions of this article **except as set**
19 **forth in Section 912**; (b) no horses shall be kept on a lot located in an R-43 district unless such
20 lot meets the minimum area regulations applicable to the district without regard to the provisions
21 of this article.

1 Section 910. Variance and Re-Zoning.

2 No variance from a plan approved under the provisions of this article shall be granted by the
3 Board of Adjustment of the Town. No application for re-zoning of all or any portion of a tract
4 zoned “CP” shall be entertained. All land designated as common land in the cluster plan finally
5 approved by the Town Council shall be used for no other purpose than a common land.

6
7 Section 911. Rescission of Cluster Plan Approval:

8 The owner of a tract of land for which a cluster plan has been approved may apply to the
9 Commission and to the Town Council, in accordance with the procedure set forth in Section 908
10 of this article, to rescind the approval of the cluster plan. If the Commission and the Town
11 Council shall be satisfied that the land use of the tract is consistent with, or will be substantially
12 restored to, the use required by the zoning in effect on the tract at the time the cluster plan was
13 approved, they may approve the application for rescission. In the event of such approval, the use
14 of the land within the tract shall be governed by the provisions applicable to the district in which
15 the tract is located as of the date the cluster plan was approved.

16
17 Section 912. Cluster Plan Adjacent to Major Arterial Streets and Floodways:

18 **The provisions of this Section 912 shall apply only to parcels of eight (8) acres or more that**
19 **meet the following criteria: (1) the parcel is adjacent to a major arterial roadway with**
20 **average daily traffic greater than 35,000 vehicles per day; (2) the parcel is adjacent to the**
21 **Indian Bend Wash; and (3) the parcel is not adjacent to an R-43 zoned area or lot.**

1 For parcels that meet the criteria of the preceding paragraph, and notwithstanding any
2 other provision in this Ordinance to the contrary, the following shall apply:
3

- 4 1. The minimum lot size shall be 16,500 square feet.
- 5 2. The maximum number of stories shall be one.
- 6 3. The minimum lot frontage shall be 100 feet.
- 7 4. Side yard setbacks with street frontage and front yard setbacks for primary
8 buildings shall be 20 feet.
- 9 5. Rear yard setbacks for primary buildings shall be 25 feet.
- 10 6. Side yard setbacks with no street frontage for primary buildings shall be 7 feet.
- 11 7. The maximum floor area ratio shall not exceed 50%.
- 12 8. Rear yard setbacks (with or without street frontage) for accessory buildings and
13 structures and pools shall be 10 feet. Front yard setbacks for accessory buildings
14 and structures and pools shall be 20 feet.
- 15 9. Side yard setbacks (with or without street frontage) for accessory buildings and
16 structures and pools shall be 7 feet. The maximum height of accessory buildings
17 and structures shall be 16 feet.
- 18 10. Front yard setbacks for garage structures that do not have a garage door facing the
19 street shall be 10 feet, provided that for all square footage of any such garage
20 between the 10 foot and 20 foot front yard setback there shall be at least an equal
21 amount of square footage behind the 20 foot setback that shall not be enclosed.

11. The height of structures shall be measured as the vertical distance from the
Regulatory Flood Elevation, as defined in Section 5-11-1 of the Town Code, adjacent
to the parcel.

SECTION 3. Severability. If any section, subsection, sentence, clause, phrase, or portion of
this ordinance or any part of these amendments to the Town Code adopted herein by reference is
for any reason held to be invalid or unconstitutional by the decision of any court of competent
jurisdiction, such decision shall not affect the validity of the remaining portions thereof.

SECTION 4. Effective Date. This ordinance shall become effective when (a) the final plat for
“The Villas at Cheney Estates” subdivision has been approved by the Town Council and
recorded with the Maricopa County Recorder’s Office and (b) the owner of the Property has
provided to the Town a duly executed Proposition 207 waiver in the form attached as Exhibit B,
which Proposition 207 waiver need not be executed and submitted to the Town until after the
final plat for “The Villas at Cheney Estates” subdivision has been approved by the Town
Council. The final plat for “The Villas at Cheney Estates” subdivision and the Proposition 207
waiver shall be recorded at the same time.

PASSED AND ADOPTED by the Mayor and Council of the Town of Paradise Valley, Arizona,
this 16th day of November 2017.

Michael Collins, Mayor

1
2 SIGNED AND ATTESTED THIS _____ DAY OF _____ 2018.

3
4 ATTEST: APPROVED AS TO FORM:

5
6
7 _____
8 Duncan Miller, Town Clerk Andrew Miller, Town Attorney

9
10

CERTIFICATION

I, Duncan Miller, Town Clerk, certify that this is a correct copy of Ordinance Number 2016-13 duly adopted by the Town Council of Paradise Valley at a meeting held on the this 16th day of November, 2017. This Ordinance appears in the minutes of the meeting, and has not been rescinded or modified and is now in effect. I further certify that the municipal corporation is duly organized and existing, *and* has the power to take the action called for by the foregoing ordinance.

Duncan Miller, Town Clerk

1
2
3

EXHIBIT A: PROPERTY DESCRIPTION

1 When recorded, return to:
2 Paradise Valley Town Attorney
3 6401 East Lincoln Drive
4 Paradise Valley, Arizona 85253

5 **ORDINANCE NUMBER 2016-14**

6 **AN ORDINANCE OF THE TOWN OF PARADISE VALLEY,**
7 **ARIZONA, AMENDING THE ZONING ORDINANCE AND**
8 **ZONING MAP OF THE TOWN OF PARADISE VALLEY**
9 **PROVIDING FOR THE REZONING OF 9.6 ACRES OF**
10 **PROPERTY LOCATED AT THE NORTHWEST CORNER OF**
11 **THE NORTHERN AVENUE ALIGNMENT AND SCOTTSDALE**
12 **ROAD - FROM R-43 SINGLE FAMILY RESIDENTIAL DISTRICT**
13 **AND SPECIAL USE PERMIT – COUNTRY CLUB AND GOLF**
14 **COURSE TO R-43 CP SINGLE FAMILY RESIDENTIAL**
15 **DISTRICT CLUSTER PLAN; PROVIDING FOR SEVERABILITY;**
16 **AND PROVIDING FOR AN EFFECTIVE DATE.**

17 WHEREAS, in accordance with Article II, Sections 1 and 2, constitution of Arizona, the
18 Town Council has considered the individual property rights and personal liberties of the
19 residents of the Town before adopting this ordinance; and

20 WHEREAS, the Town of Paradise Valley Planning Commission held a public hearing on
21 October 3, 2017, in the manner prescribed by law, for the purpose of considering Ordinance
22 2016-13, a text amendment of Article II, Definitions, and Article IX, Cluster Plan District, of the
23 Town's Zoning Ordinance, to allow for modifications to the cluster plan provisions for the
24 development known as "The Villas at Cheney Estates" regarding lot size, height measurement,
25 and setbacks, and recommended this application for Town Council approval with the effective
26 date being the same as the rezoning for said development by Ordinance 2016-14; and

27 WHEREAS, the Town of Paradise Valley Planning Commission held a public hearing on
28 October 3, 2017, in the manner prescribed by law, for the purpose of considering Ordinance

1 2016-14, a conditional rezoning of the Property from “R-43 Single Family Residential District”
2 (minimum 43,560 square foot lots) and “Special Use Permit – Country Club and Golf Course” to
3 the “R-43 Single Family Residential District Cluster Plan” (minimum 16,500 square foot lots), and
4 recommended approval to the Town Council with the conditions outlined in Section 2 of this
5 ordinance; and

6 WHEREAS, the Town of Paradise Valley Planning Commission, held a public meeting
7 on October 3, 2017, in the manner prescribed by law, for the purpose of considering an eight-lot
8 Preliminary Plat known as “The Villas at Cheney Estates,” and recommended the preliminary
9 plat application for Town Council approval; and

10 WHEREAS, as required by Section 6-2-3 of the Town Code, the final plat must be
11 presented to the Planning Commission for consideration within twelve months from the date of
12 preliminary plat approval; otherwise such preliminary approval shall become null and void
13 unless a time extension is granted by the Town Council; and

14 WHEREAS, the Town of Paradise Valley Planning Commission, held a public hearing
15 on October 3, 2017, in the manner prescribed by law, approving a private road Conditional Use
16 Permit at the development known as “The Villas at Cheney Estates,” pursuant to its authority
17 granted under Section 1103.4 of the Town’s Zoning Ordinance; and

18 WHEREAS, the Town of Paradise Valley Planning Commission, held a public hearing
19 on October 3, 2017, in the manner prescribed by law, recommending that the Town Council
20 approve Ordinance 2016-15 for a Special Use Permit (SUP) for private roadway gates at the

1 development known as “The Villas at Cheney Estates,” with the effective date being the same as
2 Ordinance 2016-14; and

3 WHEREAS, the Town of Paradise Valley Planning Commission, held a public meeting
4 on October 3, 2017, in the manner prescribed by law, for the purpose of considering two entry
5 subdivision wall signs at the development known as “The Villas at Cheney Estates,” and
6 recommended this application for Town Council approval with the effective date being the same
7 as Ordinance 2016-14; and

8 WHEREAS, the Town of Paradise Valley Town Council held a public hearing on
9 November 16, 2017, in the manner prescribed by law, for the purpose of considering Ordinance
10 2016-13, a text amendment of Article II, Definitions, and Article IX, Cluster Plan District, of the
11 Town’s Zoning Ordinance, and approved said ordinance with the effective date being the same
12 as Ordinance 2016-14; and

13 WHEREAS, the Town of Paradise Valley Council held a public hearing on November
14 16, 2017, in the manner prescribed by law, to hear and take action on Ordinance 2016-14, the
15 conditional rezoning of the Property from “R-43 Single Family Residential District” (minimum
16 43,560 square-foot lots) and “Special Use Permit – Country Club and Golf Course” to the “R-43
17 Single Family Residential District Cluster Plan” (minimum 16,500 square-foot lots), amending the
18 Zoning Ordinance and Zoning Map; and

19 WHEREAS, the Town of Paradise Valley Town Council, concurrently held a public
20 meeting/hearing on November 16, 2017, in the manner prescribed by law, to hear and take action
21 on an eight-lot Preliminary Plat known as “The Villas at Cheney Estates,” Ordinance 2016-15

1 for a Special Use Permit (SUP) for private roadway gates for said plat, and an application for two
2 entry subdivision wall signs for said plat, with the understanding that the Planning Commission
3 had granted approval of the private road Conditional Use Permit for said plat under the authority
4 of Section 1103.4 of the Town's Zoning Ordinance; and

5 WHEREAS, the rezoning to "R-43 Single Family Residential District Cluster Plan" is
6 consistent with and conforms to the both the "Low Density Residential" and "Private Open
7 Space" designations of the Land Use Map of the Town's adopted General Plan in accordance
8 with Section 306, Amendments, of the Town Code and Arizona Revised Statutes §9-462.01(F).

9 **NOW, THEREFORE, BE IT ORDAINED BY THE MAYOR AND TOWN**
10 **COUNCIL OF THE TOWN OF PARADISE VALLEY, ARIZONA THAT:**

11 SECTION 1. Rezoning. The parcel of land legally described under Exhibit A (the "Property")
12 is hereby rezoned from "R-43 Single Family Residential District" (minimum 43,560 square-foot
13 lots) and "Special Use Permit – Country Club and Golf Course" to the "R-43 Single Family
14 Residential District Cluster Plan" (minimum 16,500 square-foot lots), subject to the conditions set
15 forth in Section 2, and subject to Sections 3 and 4 of this ordinance. Promptly after the effective
16 date, the Town's Official Zoning Map shall be amended to reflect the new "R-43 Single Family
17 Residential District Cluster Plan" Zoning District; if such zoning is later invalidated, then the
18 Official Zoning Map will be changed back from "R-43 Single Family Residential District Cluster
19 Plan" to "R-43 Single Family Residential District" and "Special Use Permit – Country Club and
20 Golf Course."

21 SECTION 2. Conditions.

- 1 1. This rezoning shall apply to the property as described in the legal description prepared by
2 Eric G. Coffey, dated June 6, 2017 (the “Property”) and attached as Exhibit A.
- 3 2. Prior to the final plat of this Property being acted upon by the Planning Commission and/or
4 Town Council, the appropriate documentation shall be provided to the Town regarding
5 “The Villas at Cheney Estates” subdivision having a 100-year assured water supply.
- 6 3. The text amendment of Ordinance 2016-13, Preliminary Plat (PP-16-03), Conditional
7 Use Permit (CUP-16-02) for the private road, Special Use Permit of Ordinance 2016-15
8 (SUP-16-03) for the private roadway gates, subdivision entry signs (MI-17-03), and final
9 plat for the Property of “The Villas at Cheney Estates” first shall also be approved by the
10 Town.
- 11 4. The applicant shall provide a duly executed Proposition 207 waiver in the form attached
12 as Exhibit B as specified in Section 4 of this ordinance.
- 13 5. Prior to recordation of the final plat for this Property, an assurance shall be provided to
14 the Town to complete any improvements in the Scottsdale Road right-of-way and grading
15 within the drainage easement on lots 6 and 7 in the event the developer/owner fails to do
16 so. If Scottsdale requires an assurance for improvements in its right-of-way, a copy of
17 such assurance shall be provided to the Town but it will not be necessary for the
18 developer/owner to provide a separate assurance to the Town.
- 19 6. Prior to recordation of the final plat, the owner of the Property shall be responsible for:
20 providing an assurance to the Town for the improvement of a bicycle and/or pedestrian
21 route within, adjacent to, or nearby the Northern Avenue alignment adjoining the
22 Property; and, if needed, granting an easement to the Town to accommodate a connection
23 of the bicycle and/or pedestrian route to the existing sidewalk on Scottsdale Road. The

1 assurance shall cover the cost to install the route and landscaping adjoining the Property,
2 but shall not include the cost of relocating the utility boxes at the eastern end of the
3 Northern Avenue alignment. Such assurance shall expire five years after recordation of
4 the final plat. If the final Paradise Valley Bicycle and Pedestrian Plan as adopted by the
5 Town Council does not include a recreational path within the Northern Avenue alignment
6 between Scottsdale Road and Golf Drive, then the owner of the Property shall have no
7 obligation to install any bicycle and/or pedestrian path and the assurance shall be
8 cancelled. The owner of the Property shall not be obligated to install such bicycle and/or
9 pedestrian path until the Town has installed a similar path from Golf Drive to the western
10 edge of the Property, and in no event shall the owner of the Property be obligated to
11 relocate the utility boxes at the eastern end of the Northern Avenue alignment.

12 7. The Conditional Use Permit (CUP-16-02) for the private road, Special Use Permit
13 (Ordinance #2016-15) for the private roadway gates, and subdivision entry signs (MI-17-
14 03) for the Property of “The Villas at Cheney Estates” will become valid when the
15 Zoning Ordinance Text Amendment (Ordinance #2016-13) and Rezoning (Ordinance
16 #2016-14) for the Property become effective.

17 8. A trust indenture establishing title to the common areas must be executed in accordance
18 with Section 905, Conveyance of Common Lands, of the Zoning Ordinance.

19 9. Prior to the issuance of the first certificate of occupancy for any single-family dwelling in
20 the subdivision, the applicant shall complete the following items related to the Property:

- 21 a. Drainage and floodplain improvements;
- 22 b. Private roadway in accordance with Conditional Use Permit (CUP-16-02);
- 23 c. Water, sewer, electric, and natural gas utilities;

- d. Subdivision wall and related perimeter landscaping;
- e. Right turn deceleration lane improvements as required by the City of Scottsdale; and
- f. Private roadway gates, landscaping, and lighting of Special Use Permit (Ordinance # 2016-15).

10. Development of the Property of “The Villas at Cheney Estates” subdivision, homes, and related structures shall be in compliance with the following:

- a. All applicable Federal, State of Arizona, and Town Ordinances, including the Zoning Ordinance Text Amendment (Ordinance #2016-13) cluster plan standards;
- b. All applicable floodplain regulations, including the required improvements necessary to obtain a Letter of Map Revision (LOMR) through the Federal Emergency Management Agency; and
- c. The final plat for the Property of “The Villas at Cheney Estates.”

SECTION 3. Severability. If any section, subsection, sentence, clause, phrase, or portion of this ordinance or any part of the amendments to the Town Zoning Ordinance adopted herein by reference is for any reason held to be invalid or unconstitutional by the decision of any court of competent jurisdiction, such decision shall not affect the validity of the remaining portions thereof.

SECTION 4. Effective Date. This ordinance shall become effective when (a) the final plat for “The Villas at Cheney Estates” subdivision has been approved by the Town Council and recorded with the Maricopa County Recorder’s Office and (b) the owner of the Property has provided to the Town a duly executed Proposition 207 waiver in the form attached as Exhibit B,

1 which Proposition 207 waiver need not be submitted to the Town until after the final plat for
2 “The Villas at Cheney Estates” subdivision has been approved by the Town Council. The final
3 plat for “The Villas at Cheney Estates” subdivision and the Proposition 207 waiver shall be
4 recorded at the same time.

5 PASSED AND ADOPTED by the Mayor and Town Council of the Town of Paradise Valley,
6 Arizona, this 16th day of November, 2017.

7
8
9 _____
Michael Collins, Mayor

10
11 SIGNED AND ATTESTED TO THIS _____ DAY OF _____ 2018

12
13 ATTEST:

14
15
16 _____
17 Duncan Miller, Town Clerk

18
19 APPROVED AS TO FORM:

20
21
22
23 _____
24 Andrew M. Miller, Town Attorney

25
26
27
28 **CERTIFICATION**

29
30
31 I, Duncan Miller, Town Clerk, certify that this is a correct copy of Ordinance Number 2016-14 duly adopted by the
32 Town Council of Paradise Valley at a meeting held on the this 16th day of November, 2017. This Ordinance appears
33 in the minutes of the meeting, and has not been rescinded or modified and is now in effect. I further certify that the
34 municipal corporation is duly organized and existing, *and* has the power to take the action called for by the
35 foregoing ordinance.

36
37
38
39 _____
40 Duncan Miller, Town Clerk

1
2
3

EXHIBIT A: PROPERTY DESCRIPTION

EXHIBIT B: WAIVER OF RIGHTS AND REMEDIES (PROP 207 WAIVER)

1
2
3
4
5
6

1 When recorded, return to:
2 Paradise Valley Town Attorney
3 6401 East Lincoln Drive
4 Paradise Valley, Arizona 85253

5 **ORDINANCE NUMBER 2016-15**

6 **AN ORDINANCE OF THE TOWN OF PARADISE VALLEY,**
7 **ARIZONA, GRANTING A SPECIAL USE PERMIT FOR**
8 **PRIVATE ROADWAY ACCESS GATES AND RELATED**
9 **IMPROVEMENTS UNDER THE TERMS OF ARTICLE XI,**
10 **SPECIAL USES AND ADDITIONAL USE REGULATIONS, FOR**
11 **THE VILLAS AT CHENEY ESTATES LOCATED AT THE**
12 **NORTHWEST CORNER OF THE NORTHERN AVENUE**
13 **ALIGNMENT AND SCOTTSDALE ROAD; PROVIDING FOR**
14 **SEVERABILITY; AND PROVIDING FOR AN EFFECTIVE DATE.**

15 WHEREAS, in accordance with Article II, Sections 1 and 2, constitution of Arizona, the
16 Town Council has considered the individual property rights and personal liberties of the
17 residents of the Town before adopting this ordinance; and

18 WHEREAS, applications were filed on September 26, 2016 and July 25, 2017, on behalf
19 of Town Triangle, L.L.C., and Folkman Properties, LLC (the "Applicant") for a
20 Special Use Permit SUP-16-03 (the "Application") for private roadway gates and related
21 improvements located at the northwest corner of the Northern Avenue Alignment and Scottsdale
22 Road, Maricopa County, Arizona (the "Property"); and

23 WHEREAS, the Applicant has submitted several other applications to develop the
24 Property into eight (8) single-family residential lots, including: a Text Amendment (Ordinance
25 #2016-13) to Article II, Definitions, and Article IX, Cluster Plan District, of the Town's Zoning
26 Ordinance, to allow for modifications to the cluster plan provisions; a Rezoning (Ordinance
27 #2016-14) of the Town's Zoning Ordinance to change the zoning district from "R-43 Single

1 Family Residential District” and “Special Use Permit – Country Club and Golf Course” to “R-43
2 Single-Family Residential District Cluster Plan;” a Preliminary Plat (PP-16-03) for eight lots
3 with a minimum lot size of 16,500 square feet; and a Conditional Use Permit (CUP-16-02) to
4 make the roads within the proposed subdivision private; and

5 WHEREAS, the Town of Paradise Valley Council provided a Statement of Direction (the
6 “SOD”) to the Planning Commission at a public meeting on June 8, 2017, within the allowable
7 time limits prescribed in Article 2-5, Committees and Commissions, of the Town Code; and

8 WHEREAS, this SOD gave guidance to the Town of Paradise Valley Planning Commission
9 to evaluate the private roadway access gates for overall safety and conceptual design; and

10 WHEREAS, the Town of Paradise Valley Planning Commission held a public hearing on
11 October 3, 2017, in the manner prescribed by law, for the purpose of considering the request to
12 approve private roadway gates and related improvements on the Property, and recommended
13 approval with conditions; and

14 WHEREAS, the Town of Paradise Valley Council held a public hearing on November
15 16, 2017, in the manner prescribed by law, to hear and take action on Ordinance Number 2016-
16 15 regarding said request to approve private roadway gates and related improvements as
17 recommended by the Planning Commission; and

18
19 WHEREAS, the Town of Paradise Valley Council finds that the Applicant met the
20 requirements of Section 2-5-2.F, Citizen Review Process, including holding Citizen Review

1 sessions on October 25, 2016, November 1, 2016, September 14, 2017, and September 19, 2017
2 to provide a reasonable opportunity for the Applicant, adjacent landowners, and other potentially
3 affected citizens to discuss issues or concerns they may have with the Application; and

4 WHEREAS, Mobility Policy 4.4.1.2 of the Town of Paradise Valley General Plan
5 discourages the installation of private roadway gates. However, given the access and proximity of
6 the subject property onto the major arterial of Scottsdale Road, the constraints in improving the
7 Northern Avenue alignment, and the existence of private roadway gates for residential subdivisions
8 along Scottsdale Road being common, private roadway gates are justified in this instance.

9 **NOW, THEREFORE, BE IT ORDAINED BY THE MAYOR AND TOWN COUNCIL OF**
10 **THE TOWN OF PARADISE VALLEY, ARIZONA THAT:**

11 SECTION 1. The Property is granted the use and installation of private roadway access gates
12 and related improvements subject to the conditions set forth in Section 2, and subject to Section
13 4 of this ordinance.

14 SECTION 2. Conditions.

15 1. SUP-16-03 shall allow for private roadway gates and related improvements on portions
16 of the property described in the legal description prepared by Eric G. Coffey, dated June
17 6, 2017 (the “Gate Property”) and attached as Exhibit A.

18 2. All improvements shall be in substantial compliance with the following:

- 19 a. The concept plan, concept details, planting plan, hardscape plan, and lighting plan
20 prepared by Refined Gardens, dated May 2016, attached as Exhibit B, and
21 b. The Wall and Gate Plan prepared by Cullum Homes and Strong-Kennedy
22 Architects attached as Exhibit C.

- 1 3. The related applications to develop the Property first shall also be approved by the Town,
2 specifically the Text Amendment (Ordinance #2016-13), Rezoning (Ordinance #2016-
3 14), Preliminary Plat (PP-16-03), Conditional Use Permit (CUP-16-02), and Subdivision
4 Signs (MI-17-03), along with recordation of the final plat for the Property.
- 5 4. Lighting in the gate area shall comply with the Town Code and the Town Special Use
6 Permit Guidelines, with details on all lighting such as location, quantities, fixture type,
7 lumens, and foot-candle requirements to be as generally shown on the referenced plans of
8 Condition 2. The referenced plans of Condition 2 shall control in the event of an
9 inconsistency. All landscaping in the gate area shall comply with the Town Landscape
10 Guidelines, with details on location, quantities, plant type, and plant size to be as
11 generally shown on the referenced plans of Condition 2.
- 12 5. The owner of the Property, or successors, shall provide the Town, in a form acceptable to
13 the Town Attorney, a grant of access easement and a private roadway maintenance
14 agreement for the private roadway, private roadway gates, emergency access gate, and
15 any related roadway/gate improvements on the Gate Property. This form shall be
16 reviewed by the Town Attorney, be in compliance to applicable local and state laws, and
17 be recorded with the Maricopa County Recorder's Office. Said form shall be recorded
18 prior to or on the effective date of this ordinance.
- 19 6. To minimize impact of stacking by motorized vehicle use near the entry gates, the
20 developer and/or homeowner association shall contract with one landscape maintenance
21 provider for lot and tract maintenance.

1 SECTION 3. Severability. If any section, subsection, sentence, clause, phrase, or portion of
2 this ordinance or any part of this ordinance is for any reason held to be invalid or
3 unconstitutional by the decision of any court of competent jurisdiction, such decision shall not
4 affect the validity of the remaining portions thereof.

5 SECTION 4. Effective Date. This ordinance shall become effective when (a) the final plat for
6 “The Villas at Cheney Estates” subdivision has been approved by the Town Council and
7 recorded with the Maricopa County Recorder’s Office and (b) the owner of the Property has
8 provided to the Town a duly executed Proposition 207 waiver in the form attached as Exhibit B,
9 which Proposition 207 waiver need not be submitted to the Town until after the final plat for
10 “The Villas at Cheney Estates” subdivision has been approved by the Town Council. The final
11 plat for “The Villas at Cheney Estates” subdivision and the Proposition 207 waiver shall be
12 recorded at the same time.

13 PASSED AND ADOPTED by the Mayor and Town Council of the Town of Paradise Valley,
14 Arizona, this 16th day of November, 2017.

15
16
17 _____
18 Michael Collins, Mayor

19 SIGNED AND ATTESTED TO THIS _____ DAY OF _____ 2018

20
21 ATTEST:

22
23
24 _____
25 Duncan Miller, Town Clerk

26
27 APPROVED AS TO FORM:

28
29
30 _____
31 Andrew M. Miller, Town Attorney
32
33

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54

CERTIFICATION

I, Duncan Miller, Town Clerk, certify that this is a correct copy of Ordinance Number 2016-15 duly adopted by the Town Council of Paradise Valley at a meeting held on the this 16th day of November, 2017. This Ordinance appears in the minutes of the meeting, and has not been rescinded or modified and is now in effect. I further certify that the municipal corporation is duly organized and existing, *and* has the power to take the action called for by the foregoing ordinance.

Duncan Miller, Town Clerk



1
2

EXHIBIT A: PROPERTY DESCRIPTION

1
2
3
4
5
6

EXHIBIT B: PLANS

CONCEPT PLAN, CONCEPT DETAILS, PLANTING PLAN, HARDSCAPE PLAN,
AND LIGHTING PLAN PREPARED BY REFINED GARDENS, DATED MAY 2016



 CULLUM HOMES www.cullumhomes.com	VILLAS AT CHENEY ESTATES
	STRONG · KENNEDY ARCHITECTS 480-577-3773

IRONWOOD GOLF VILLAS

PARADISE VALLEY, ARIZONA

REFINED GARDENS
DESIGN • BUILD • MAINTAIN



DATE
MAY 2016



REVISIONS


A
B
C
D

DRAWING
CONCEPT PLAN
SHEET

L-0-0 of 1

PLANT LIST				
ID	BOTANICAL	COMMON	SIZE	QTY.
TREES				
TP	Tipuana Tipu	Tipu	BOX	
TE	Elaeagnus argentea	Texas Ebony	BOX	
IR	Ironwood	Ironwood	BOX	
AGAVE				
	Agave weberi	Weber's Agave	gallon	
	Agave victoriae-reginae	Queen Victoria Agave	gallon	
SHRUBS				
	Dodonaea viscosa	Hopseed bush	gallon	
	Muhlenbergia capillaris 'Regal Mist'	Regal Mist	gallon	
	Convolvulus cneorum	Bush Morning Glory	gallon	
GROUND COVER				
	Myoporum parvifolium	Myoporum	gallon	
	Acacia redolens	Desert Carpet Acacia	gallon	
VINES				
	Bougainvillea 'Barbara Karst'	Bougainvillea	gallon	





16' 32' 64'
SCALE: 1/32"=1'



Any and all dimensions shown on this plan are for informational purposes only. Dimensions shown on this plan are not to be used for construction purposes. Dimensions shown on this plan are not to be used for construction purposes.



1"=1' HOLLAND NONTUMBER (PAGES 3) TONE BROWN LAD IN HARDING BOND ANTERAL
SAND SET WITH MORTAR BORDER

HARDSCAPE SCHEDULE

PAVING

- 111 DRYWALL CONCRETE PAVERS, TID, SET IN RUNNING BOND FOLLOWING ROUNDABOUT, LIGHT GRAY COLOR
- 112 DRYWALL CONCRETE PAVERS, TID, SET IN RUNNING BOND FOLLOWING ROUNDABOUT, GRAY COLOR
- 113 2" W CONCRETE BAND COLOR TID
- 114 PEDESTRIAN WALKWAY PAVES TID, RUNNING BOND SET
- 115 DECOMPOSED GRANITE SIZE AND COLOR TID
- 116 N/A
- 117 CONCRETE HEADER PER CIVIL ENGINEER
- 118 ASPHALT PER CIVIL ENGINEER
- 119 SIDEWALK PER CIVIL ENGINEER

WALLS

- W1 6" H CMU WALLS PER CIVIL ENGINEER, FINISH TID

COLUMNS



- C1 6" H CMU COLUMNS PER CIVIL ENGINEER, W/ 1/2" X 2" CAP FINISH TID
- C2 6" H CMU COLUMNS PER CIVIL ENGINEER, W/ 1/2" X 2" CAP FINISH TID

GATES

- G1 2" W METAL PEDESTRIAN GATE
- G2 21" W RECTANGULAR METAL GATE

ADORNMENTS

- A1 CALL BOX, SEE ARCHITECTURAL DRAWINGS
- A2 WATER FEATURE MAIN ENTRY
- A3 PROJECT SIGNAGE



THIS PLAN IS THE PROPERTY OF THE DESIGNER AND IS NOT TO BE REPRODUCED OR COPIED IN ANY MANNER WITHOUT THE WRITTEN CONSENT OF THE DESIGNER. THE DESIGNER ASSUMES NO LIABILITY FOR ANY DAMAGE OR INJURY TO PERSONS OR PROPERTY ARISING FROM THE USE OF THIS PLAN.

IRONWOOD GOLF VILLAS

PARADISE VALLEY, ARIZONA

REFINED GARDENS
DESIGN - BUILD - MAINTAIN



7117 EAST RANCHO VISTA DRIVE SUITE 101
SCOTTSDALE, AZ 85251
480.586.2106 REFINEDGARDENS.COM

DATE
MAY 2016
REVISIONS


A

DRAWING:
CONCEPT DETAILS
SHEET

L2.0 of 5



ENTRY WATER FEATURE




ENTRY GATE





PLANT LIST PHASE 02




ID	BOTANICAL	COMMON	SIZE	QTY.
TREES				
17	Tipuana Tipu	Tipu	24" BOX	4
18	Elaeagnus elaeagnifolia	Tea Tree	36" BOX	6
19	Quercus agrifolia	Ironwood	60" BOX	2
AGAVE				
20	Agave weberi	Weber's Agave	1 gallon	40
21	Agave victoriae-reginae	Queen Victoria Agave	1 gallon	20
SHRUBS				
22	Dodonaea viscosa	Hopseed bush	1 gallon	302
23	Muhlenbergia capillaris	Regal Mist	1 gallon	80
24	Convolvulus cneorum	Bush Morning Glory	1 gallon	18
GROUND COVER				
25	Myoporum parvifolium	Myoporum	1 gallon	30
26	Acacia redolens	Desert Carpet Acacia	1 gallon	16
VINES				
27	Bougainvillea 'Barbara Karst'	Bougainvillea	1 gallon	6





LIGHTING SCHEDULE

ID	FIXTURE NAME	MANUFACTURE	MODEL	FINISH	TYPE	QTY
1	PATH LIGHT- 18" HIGHER	FX LUMINAIRE	* HC- 18" pedestal top & base	BRONZE METALIC	3 LED	17
2	UP LIGHT	FX LUMINAIRE	* FB	BRONZE METALIC	3 LED	26
3	UP LIGHT- WASH	FX LUMINAIRE	* PB	BRONZE METALIC	3 LED	12
4	WATER LIGHT	FX LUMINAIRE	* LL	NATURAL BRASS	1 LED	4
5	TRANSFORMER	FX LUMINAIRE	PX- 600W			



PROJECT SIGNAGE



4" 8" 16"

SCALE: 1/8"=1'



SHEET 4/5



Any mechanical equipment, such as air conditioning units, should be located away from the building and the parking area. The location of the equipment should be determined by the mechanical engineer.

1
2
3
4
5
6

EXHIBIT C: PLANS
THE WALL AND GATE PLAN PREPARED BY CULLUM HOMES AND
STRONG-KENNEDY ARCHITECTS



When recorded, return to:
Paradise Valley Town Attorney
6401 East Lincoln Drive
Paradise Valley, Arizona 85253

WAIVER OF RIGHTS AND REMEDIES

UNDER A.R.S. § 12-1134

This agreement regarding Waiver of Rights and Remedies under A.R.S. § 12-1134 (this "Agreement") is made on this _____ day of _____, 2018, between TOWN TRIANGLE, LLC, an Arizona limited liability company, and FOLKMAN PROPERTIES, LLC, an Arizona limited liability company (collectively, "Owner"), and the TOWN OF PARADISE VALLEY, an Arizona municipal corporation (the "Town"), regarding the property located in the Town at the northwest corner of the Northern Avenue alignment and Scottsdale Road, which is more particularly described by the legal description (the "Property," attached hereto as Exhibit A).

The Owner agrees and consents to all the conditions of approval (the "Conditions of Approval," attached hereto as Exhibit B) that are set forth in the final approvals by the Town Council and/or Planning Commission regarding the following applications related to the Property: Text Amendment (Ordinance #2016-13) to Article II, Definitions, and Article IX, Cluster Plan District, of the Town's Zoning Ordinance, to allow for modifications to the cluster plan provisions for this proposed development such as lot size, height measurement, and setbacks; Rezoning (Ordinance #2016-14) to change the zoning district from "R-43 Single Family Residential District" and "Special Use Permit – Country Club and Golf Course" to the "R-43 Single Family Residential District Cluster Plan"; Preliminary Plat (PP-16-03) for up to eight residential single-family lots; Conditional Use Permit (CUP-16-02) to make the road(s) within the proposed subdivision private; Special Use Permit (Ordinance #2016-15) for private roadway gates; Subdivision Signs (MI-17-03), and Final Plat.

The Owner has voluntarily applied for the change in its land use entitlements referenced in these above applications; and agrees that the Conditions of Approval to develop an up to eight-lot single-family residential subdivision on the Property do not diminish the value of the Property.

By signing this Agreement, the Owner acknowledges that the Owner waives any right to claim diminution in value or claim for just compensation for diminution in value with regard to the Property under A.R.S. § 12-1134 related to the approval of said applications.

This Agreement, any exhibits attached hereto, and any addendum, constitute the entire understanding and agreement of the Owner and the Town and shall supersede all prior agreements or understandings between the Owner and the Town only with respect to said applications. This Agreement may not be modified or amended except by written agreement by the Owner and the Town.

This Agreement is entered into in Arizona and will be construed and interpreted under the laws of the State of Arizona.

This Agreement shall become effective when the final plat for "The Villas at Cheney Estates" is recorded in the Official Records of the County Recorder's Office, Maricopa County, Arizona. The Town Clerk shall file this Agreement in the Official Records of the County Recorder's Office, Maricopa County, Arizona at the same time that the final plat for said plat is recorded.

This Agreement runs with the land and is binding upon all present and future owners of the Property.

This Agreement is subject to the cancellation provisions of A.R.S. § 38-511.

The Owner warrants and represents that TOWN TRIANGLE, LLC and FOLKMAN PROPERTIES, LLC are the owners of fee title to the Property.

Dated this _____ day of _____, 2018.

"OWNER"

TOWN TRIANGLE, LLC, an Arizona limited liability company

By: _____

Name: _____

Title: _____

State of Arizona)
) ss

County of Maricopa)

SUBSCRIBED AND SWORN to before me this _____ day of _____, 2018
by _____, the _____ of TOWN TRIANGLE, LLC, an Arizona
limited liability company, for and on behalf thereof.

My commission expires: _____
Notary Public

"OWNER"

FOLKMAN PROPERTIES, LLC, an Arizona limited liability company

By: _____

Name: _____

Title: _____

State of Arizona)
) ss

County of Maricopa)

SUBSCRIBED AND SWORN to before me this _____ day of _____, 2018
by _____, the _____ of FOLKMAN PROPERTIES, LLC, an
Arizona limited liability company, for and on behalf thereof.

My commission expires: _____
Notary Public

"TOWN"

TOWN OF PARADISE VALLEY,
an Arizona municipal corporation

Kevin Burke, Town Manager

ATTEST:

Duncan Miller, Town Clerk

APPROVED AS TO FORM:

Andrew Miller, Town Attorney

EXHIBIT A: PROPERTY

EXHIBIT B: CONDITIONS OF APPROVAL

The Conditions of Approval for the Property of "The Villas at Cheney Estates," are as follows:

Zoning Ordinance Text Amendment (MI-16-03)

Subject to Ordinance Number 2016-13, providing for severability and providing for an effective date.

Rezoning (MI-16-04)

Subject to Ordinance Number 2016-14 that includes the following conditions:

1. This rezoning shall apply to the property as described in the legal description prepared by Eric G. Coffey, dated June 6, 2017 (the "Property") and attached as Exhibit A.
2. Prior to the final plat of this Property being acted upon by the Planning Commission and/or Town Council, the appropriate documentation shall be provided to the Town regarding "The Villas at Cheney Estates" subdivision having a 100-year assured water supply.
3. The text amendment of Ordinance 2016-13, Preliminary Plat (PP-16-03), Conditional Use Permit (CUP-16-02) for the private road, Special Use Permit of Ordinance 2016-15 (SUP-16-03) for the private roadway gates, subdivision entry signs (MI-17-03), and final plat for the Property of "The Villas at Cheney Estates" first shall also be approved by the Town.
4. The applicant shall provide a duly executed Proposition 207 waiver in the form attached as Exhibit B as specified in Section 4 of this ordinance.
5. Prior to recordation of the final plat for this Property, an assurance shall be provided to the Town to complete any improvements in the Scottsdale Road right-of-way and grading within the drainage easement on lots 6 and 7 in the event the developer/owner fails to do so. If Scottsdale requires an assurance for improvements in its right-of-way, a copy of such assurance shall be provided to the Town but it will not be necessary for the developer/owner to provide a separate assurance to the Town.
6. Prior to recordation of the final plat, the owner of the Property shall be responsible for: providing an assurance to the Town for the improvement of a bicycle and/or pedestrian route within, adjacent to, or nearby the Northern Avenue alignment adjoining the Property; and, if needed, granting an easement to the Town to accommodate a connection of the bicycle and/or pedestrian route to the existing sidewalk on Scottsdale Road. The assurance shall cover the cost to

install the route and landscaping adjoining the Property, but shall not include the cost of relocating the utility boxes at the eastern end of the Northern Avenue alignment. Such assurance shall expire five years after recordation of the final plat. If the final Paradise Valley Bicycle and Pedestrian Plan as adopted by the Town Council does not include a recreational path within the Northern Avenue alignment between Scottsdale Road and Golf Drive, then the owner of the Property shall have no obligation to install any bicycle and/or pedestrian path and the assurance shall be cancelled. The owner of the Property shall not be obligated to install such bicycle and/or pedestrian path until the Town has installed a similar path from Golf Drive to the western edge of the Property, and in no event shall the owner of the Property be obligated to relocate the utility boxes at the eastern end of the Northern Avenue alignment.

7. The Conditional Use Permit (CUP-16-02) for the private road, Special Use Permit (Ordinance #2016-15) for the private roadway gates, and subdivision entry signs (MI-17-03) for the Property of “The Villas at Cheney Estates” will become valid when the Zoning Ordinance Text Amendment (Ordinance #2016-13) and Rezoning (Ordinance #2016-14) for the Property become effective.
8. A trust indenture establishing title to the common areas must be executed in accordance with Section 905, Conveyance of Common Lands, of the Zoning Ordinance.
9. Prior to the issuance of the first certificate of occupancy for any single-family dwelling in the subdivision, the applicant shall complete the following items related to the Property:
 - a. Drainage and floodplain improvements;
 - b. Private roadway in accordance with Conditional Use Permit (CUP-16-02);
 - c. Water, sewer, electric, and natural gas utilities;
 - d. Subdivision wall and related perimeter landscaping;
 - e. Right turn deceleration lane improvements as required by the City of Scottsdale; and
 - f. Private roadway gates, landscaping, and lighting of Special Use Permit (Ordinance #2016-15).
10. Development of the Property of “The Villas at Cheney Estates” subdivision, homes, and related structures shall be in compliance with the following:
 - a. All applicable Federal, State of Arizona, and Town Ordinances, including the Zoning Ordinance Text Amendment (Ordinance #2016-13) cluster plan standards;

- b. All applicable floodplain regulations, including the required improvements necessary to obtain a Letter of Map Revision (LOMR) through the Federal Emergency Management Agency; and
- c. The final plat for the Property of “The Villas at Cheney Estates.”

Preliminary Plat (PP-16-03)

1. The final plat for “The Villas at Cheney Estates” shall be in substantial compliance with the Preliminary Plat, Sheets 1-3, prepared by CVL Consultants, dated August 31, 2017.
2. Prior to the final plat of this Property being approved by the Town Council, the appropriate documentation shall be provided to the Town regarding “The Villas at Cheney Estates” subdivision having a 100-year assured water supply.
3. A final subdivision wall and landscape plan shall be approved with the final plat for “The Villas at Cheney Estates.” This plan shall exclude the areas approved under the Special Use Permit of Ordinance 2016-15 (SUP-16-03) related to the private roadway gates, walls, and other improvements/landscaping depicted on such plan.
4. Prior to recordation of the final plat for said subdivision, the applicant shall provide to the Town Attorney a copy of the CC&R’s or other documents for review.
5. Within 60 days of approval of the final plat, the applicant shall submit to the Town mylars of the approved plans and an electronic version of these plans in a pdf format for the Town’s permanent record.

Conditional Use Permit (CUP-16-02)

1. This private roadway Conditional Use Permit (CUP) shall apply to the property as described in the legal description prepared by Eric G. Coffey dated September 11, 2017 (the “Property”).
2. This CUP shall be in substantial compliance with the roadway cross-sections as shown on the Preliminary Plat prepared by CVL Consultants, dated August 31, 2017, which are in general conformance with the Typical Local Cross-Section, Option B, of the Town’s General Plan.
3. The owner of the Property shall provide the Town a grant of access easement over the private roadway and a private roadway maintenance agreement pursuant to Ordinance Number 2016-15, allowing for private roadway gates of SUP-16-03.

Special Use Permit (SUP-16-03)

Subject to Ordinance Number 2016-15 that includes the following conditions:

1. SUP-16-03 shall allow for private roadway gates and related improvement on portions of the property described in the legal description prepared by Eric G. Coffey, dated June 6, 2017 (the "Gate Property") and attached as Exhibit A.
2. All improvements shall be in substantial compliance with the following:
 - a. The concept plan, concept details, planting plan, hardscape plan, and lighting plan prepared by Refined Gardens, dated May 2016, attached as Exhibit B, and
 - b. The Wall and Gate Plan prepared by Cullum Homes and Strong-Kennedy Architects attached as Exhibit C.
3. The related applications to develop the Property first shall also be approved by the Town, specifically the Text Amendment (Ordinance #2016-13), Rezoning (Ordinance #2016-14), Preliminary Plat (PP-16-03), Conditional Use Permit (CUP-16-02), and Subdivision Signs (MI-17-03), along with recordation of the final plat for the Property.
4. Lighting in the gate area shall comply with the Town Code and the Town Special Use Permit Guidelines, with details on all lighting such as location, quantities, fixture type, lumens, and foot-candle requirements to be as generally shown on the referenced plans of Condition 2. The referenced plans of Condition 2 shall control in the event of an inconsistency.
5. All landscaping in the gate area shall comply with the Town Landscape Guidelines, with details on location, quantities, plant type, and plant size to be as generally shown on the referenced plans of Condition 2.
6. The owner of the Property, or successors, shall provide the Town, in a form acceptable to the Town Attorney, a grant of access easement and a private roadway maintenance agreement for the private roadway, private roadway gates, emergency access gate, and any related roadway/gate improvements on the Gate Property. This form shall be reviewed by the Town Attorney, be in compliance to applicable local and state laws, and be recorded with the Maricopa County Recorder's Office. Said form shall be recorded prior to or on the effective date of this ordinance.
7. To minimize impact of stacking by motorized vehicle use near the entry gates, the developer and/or homeowner association shall contract with one landscape maintenance provider for lot and tract maintenance.

Subdivision Signs (MI-17-03)

1. Subdivision signage and sign lighting for the Property of “The Villas at Cheney Estates” shall be in substantial compliance with the Wall and Gate Plan prepared by Cullum Homes.
2. Sign lighting shall not exceed two fixtures per sign, each fixture shall not exceed a lumen count of 1,080 lumens, and the illumination shall not exceed 0.75 foot-candles at the property line.

Final Plat (FP-18-)

[Add conditions]

June 6, 2017

LEGAL DESCRIPTION FOR
VILLAS AT CHENEY ESTATES

That part of the Southeast Quarter of Section 34, Township 3 North, Range 4 East of the Gila and Salt River Meridian, Maricopa County, Arizona, more particularly described as follows:

Commencing at the Brass Cap in hand hole marking the Southeast Corner of said Section 34, from which the Brass Cap in hand hole marking the East Quarter Corner of said Section 34 bears North 00°00'00" East, a distance of 2,640.81 feet;

Thence North 00°00'00" East, along the East line of the Southeast Quarter of said Section 34, a distance of 40.00 feet to a point on a line which is parallel with and 40.00 feet Northerly, as measured at right angles, from the South line of the Southeast Quarter of said Section 34;

Thence North 89°45'30" West, along said parallel line, a distance of 77.05 feet to the True Point of Beginning;


Thence continuing North 89°45'30" West, a distance of 784.84 feet;

Thence North 37°11'31" East, a distance of 1,318.29 feet to a point on a line which is parallel with and 65.00 feet Westerly, as measured at right angles, from the East line of the Southeast Quarter of said Section 34;

Thence South 00°00'00" East, along said parallel line, a distance of 1,041.48 feet to the beginning of a tangent curve of 12.00 foot radius, concave Northwesterly;

Thence Southwesterly, along said curve, through a central angle of 90°14'30", a distance of 18.90 feet to the True Point of Beginning.

Containing 419,740 Square Feet or 9.636 Acres, more or less.



EAST 1/4 CORNER
SECTION 34
TOWNSHIP 3 NORTH
RANGE 4 EAST


LINE TABLE		
NO.	BEARING	LENGTH
L1	N00°00'00"E	40.00'
L2	N89°45'30"W	77.05'



= VILLAS AT
CHENEY ESTATES


SOUTH 1/4 CORNER
SECTION 34
TOWNSHIP 3 NORTH
RANGE 4 EAST

NORTHERN AVENUE (ALIGNMENT)



POINT OF COMMENCEMENT
SOUTHEAST CORNER
SECTION 34
TOWNSHIP 3 NORTH
RANGE 4 EAST

SCOTTSDALE ROAD



SCALE 1" = 200'

EXHIBIT

VILLAS AT CHENEY ESTATES

4550 North 12th Street
Phoenix, Arizona 85014
Phone 602-264-6831
<http://www.cvlci.com>



1 OF 1

September 11, 2017

LEGAL DESCRIPTION FOR
VILLAS AT CHENEY ESTATES
PRIVATE STREET EASEMENT

That part of the Southeast Quarter of Section 34, Township 3 North, Range 4 East of the Gila and Salt River Meridian, Maricopa County, Arizona, more particularly described as follows:

Commencing at the Brass Cap in hand hole marking the Southeast Corner of said Section 34, from which the Brass Cap in hand hole marking the East Quarter Corner of said Section 34 bears North 00°00'00" East, a distance of 2,640.81 feet;

Thence North 00°00'00" West, along the East line of the Southeast Quarter of said Section 34, a distance of 387.64 feet;

Thence North 90°00'00" West, a distance of 65.00 feet to the True Point of Beginning;

Thence continuing South 90°00'00" West, a distance of 1.99 feet;

Thence South 37°04'36" West, a distance of 189.75 feet; to the beginning of a tangent curve of 12.00 foot radius, concave Easterly;

Thence Southerly, along said curve, through a central angle of 42°05'34", a distance of 8.82 feet; to the beginning of a tangent reverse curve of 55.00 foot radius, concave Southwesterly;

Thence Northwesterly, along said curve, through a central angle of 290°50'38", a distance of 279.19 feet; to the beginning of a tangent reverse curve of 12.00 foot radius, concave Northerly;

Thence Easterly, along said curve, through a central angle of 68°45'05", a distance of 14.40 feet;

Thence North 37°04'36" East, a distance of 88.66 feet; to the beginning of a tangent curve of 30.00 foot radius, concave Westerly;

Thence Northerly, along said curve, through a central angle of 68°09'16", a distance of 35.69 feet; to the beginning of a tangent reverse curve of 45.00 foot radius, concave Easterly;

Thence Northerly, along said curve, through a central angle of 82°00'14", a distance of 64.41 feet;

Thence North 37°11'31" East, a distance of 132.88 feet to a point on a line which is parallel with and 65.00 feet Westerly, as measured at right angles, from the East line of the Southeast Quarter of said Section 34;

Legal Description for
Villas at Cheney Estates
Private Street Easement
September 11, 2017

Thence South 00°00'00" East, along said parallel line, a distance of 161.07 feet to the True Point of Beginning.


Containing 27,491 Square Feet or 0.6311 Acres, more or less.



Expires: 3/31/20

EAST 1/4 CORNER, SECTION 34
TOWNSHIP 3 NORTH, RANGE 4 EAST


TRUE POINT OF BEGINNING



POINT OF COMMENCEMENT
SOUTHEAST CORNER, SECTION 34
TOWNSHIP 3 NORTH, RANGE 4 EAST



PRIVATE
= STREET
EASEMENT



SCALE 1" = ___'

EXHIBIT

4550 North 12th Street
Phoenix, Arizona 85014
Phone 602-264-6831
<http://www.cvlci.com>

VILLAS AT CHENEY ESTATES

PRIVATE STREET EASEMENT



1 OF 2

CURVE TABLE

NO.	LENGTH	RADIUS	DELTA	TANGENT	CHORD	CHORD-BEARING
C1	8.82'	12.00'	042°05'34"	4.62'	8.62'	S16°01'49"W
C2	279.19'	55.00'	290°50'38"	37.91'	62.43'	N39°35'38"W
C3	14.40'	12.00'	068°45'05"	8.21'	13.55'	N71°27'09"E
C4	35.69'	30.00'	068°09'16"	20.29'	33.62'	N02°59'58"E
C5	64.41'	45.00'	082°00'14"	39.12'	59.05'	N09°55'28"E

LINE TABLE

NO.	BEARING	LENGTH
L1	N90°00'00"W	65.00'
L2	S90°00'00"W	1.99'
L3	S37°04'36"W	189.75'
L4	N37°04'36"E	88.66'
L5	N37°11'31"E	132.88'
L6	S00°00'00"E	161.07'



SCALE: NONE

EXHIBIT

4550 North 12th Street
Phoenix, Arizona 85014
Phone 602-264-6831
<http://www.cvlci.com>

VILLAS AT CHENEY ESTATES

PRIVATE STREET EASEMENT



2 OF 2