

SUMMIT

LAND MANAGEMENT

PHOENIX COUNTRY DAY SCHOOL PERFORMING ARTS CENTER Paradise Valley, Arizona

Traffic Impact Analysis - REVISED

December 2023

Prepared for:

PHOENIX COUNTRY DAY SCHOOL

For Submittal to:

TOWN OF PARADISE VALLEY

Prepared by: Paul E. Basha, PE, PTOE
Kayla Bertoldo

Office: 480.505.3931
pbasha@summitlandmgmt.com



SUMMIT LAND MANAGEMENT
7144 E Stetson Drive Suite 300
Scottsdale Arizona 85251

Table of Contents

Executive Summary	1
<i>Introduction</i>	1
<i>Results</i>	1
<i>Recommendations without Performing Arts Center</i>	2
<i>Recommendations with Performing Arts Center</i>	2
Introduction.....	3
Scope of Study	4
Surrounding Transportation System.....	5
Collision Analysis	6
Existing Traffic Volumes.....	8
Future Ambient 2025	23
Planned Events at Performing Arts Center.....	29
Proposed Performing Arts Center Estimated Trip Generation	29
Level-of-Service Analysis.....	39
<i>Results</i>	40
<i>Conclusions</i>	41
<i>Recommendations without Performing Arts Center</i>	41
<i>Recommendations with Performing Arts Center</i>	41

List of Figures

Figure 1: General Vicinity Aerial Photograph.....	3
Figure 2: Immediate Vicinity Aerial Photograph.....	4
Figure 3: Intersection Existing Lane Configurations	5
Figure 4: Phoenix Country Day School Performing Arts Center Site Plan	6
Figure 5: 24 Hour Counts at 40 th / Stanford.....	9
Figure 6: 6:00 AM to 7:30 PM 60-Minute Counts at 40 th / Stanford with Analyzed Hours Indicated	10
Figure 7: Existing 2023 Day Approach and Departure Volumes.....	11
Figure 8: Existing 2023 7:15 to 8:15 AM Peak Hour Approach and Departure Volumes.....	12
Figure 9: Existing 2023 7:15 to 8:15 AM Peak Hour Turning Movement Volumes.....	12
Figure 10: Existing 2023 2:30 to 3:30 PM Peak Hour Approach and Departure Volumes.....	13
Figure 11: Existing 2023 2:30 to 3:30 PM Peak Hour Turning Volumes	13
Figure 12: Existing 2023 4:30 to 5:30 PM Peak Hour Approach and Departure Volumes.....	14
Figure 13: Existing 2023 4:30 to 5:30 PM Peak Hour Turning Volumes	14
Figure 14: Existing 2023 5:30 to 6:30 PM Peak Hour Approach and Departure Volumes.....	15
Figure 15: Existing 2023 5:30 to 6:30 PM Peak Hour Turning Volumes	15
Figure 16: Existing 2023 7:00 to 8:00 PM Peak Hour Approach and Departure Volumes.....	16
Figure 17: Existing 2023 7:00 to 8:00 PM Peak Hour Turning Volumes	16
Figure 18: Adjusted 2023 Day Approach and Departure Volumes	17
Figure 19: Adjusted 2023 7:15 to 8:15 AM Peak Hour Approach and Departure Volumes	18
Figure 20: Adjusted 2023 7:15 to 8:15 AM Peak Hour Turning Movement Volumes	18
Figure 21: Adjusted 2023 2:30 to 3:30 PM Peak Hour Approach and Departure Volumes	19
Figure 22: Adjusted 2023 2:30 to 3:30 PM Peak Hour Turning Volumes.....	19
Figure 23: Adjusted 2023 4:30 to 5:30 PM Peak Hour Approach and Departure Volumes	20

Figure 24: Adjusted 2023 4:30 to 5:30 PM Peak Hour Turning Volumes..... 20

Figure 25: Adjusted 2023 5:30 to 6:30 PM Peak Hour Approach and Departure Volumes 21

Figure 26: Adjusted 2023 5:30 to 6:30 PM Peak Hour Turning Volumes..... 21

Figure 27: Adjusted 2023 7:00 to 8:00 PM Peak Hour Approach and Departure Volumes 22

Figure 28: Adjusted 2023 7:00 to 8:00 PM Peak Hour Turning Volumes..... 22

Figure 29: Ambient 2025 Day Approach and Departure Volumes 23

Figure 30: Ambient 2025 7:15 to 8:15 AM Peak Hour Approach and Departure Volumes 24

Figure 31: Ambient 2025 7:15 to 8:15 AM Peak Hour Turning Movement Volumes 24

Figure 32: Ambient 2025 2:30 to 3:30 PM Peak Hour Approach and Departure Volumes 25

Figure 33: Ambient 2025 2:30 to 3:30 PM Peak Hour Turning Volumes..... 25

Figure 34: Ambient 2025 4:30 to 5:30 PM Peak Hour Approach and Departure Volumes 26

Figure 35: Ambient 2025 4:30 to 5:30 PM Peak Hour Turning Volumes..... 26

Figure 36: Ambient 2025 5:30 to 6:30 PM Peak Hour Approach and Departure Volumes 27

Figure 37: Ambient 2025 5:30 to 6:30 PM Peak Hour Turning Volumes..... 27

Figure 38: Ambient 2025 7:00 to 8:00 PM Peak Hour Approach and Departure Volumes 28

Figure 39: Ambient 2025 7:00 to 8:00 PM Peak Hour Turning Volumes..... 28

Figure 40: Aerial Photograph of Greater Vicinity of Phoenix Country Day School 30

Figure 41: Street Schematic of Greater Vicinity of Phoenix Country Day School..... 31

Figure 42: PCDS Performing Arts Center Day Approach and Departure Volumes 32

Figure 43: PCDS PAC 5:30 to 6:30 PM Peak Hour Approach and Departure Volumes..... 33

Figure 44: PCDS Performing Arts Center 5:30 to 6:30 PM Peak Hour Turning Movement Volumes 33

Figure 45: PCDS PAC 7:00 to 8:00 PM Peak Hour Approach and Departure Volumes..... 34

Figure 46: PCDS Performing Arts Center 7:00 to 8:00 PM Peak Hour Turning Movement Volumes 34

Figure 47: 2025 with PCDS Performing Arts Center Day Approach and Departure Volumes 35

Figure 48: 2025 with PCDS PAC 5:30 to 6:30 PM Peak Hour Approach and Departure Volumes..... 35

Figure 49: 2025 with PCDS Performing Arts Center 5:30 to 6:30 PM Peak Hour Turning Volumes 36

Figure 50: 2025 with PCDS PAC 7:00 to 8:00 PM Peak Hour Approach and Departure Volumes..... 36

Figure 51: 2025 with PCDS Performing Arts Center 7:00 to 8:00 PM Peak Hour Turning Volumes 37

Figure 52: 2025 with PCDS Performing Arts Center Traffic Volume – School Access..... 38

List of Tables

Table 1: Peak Hours Level-of-Service Summary for 40th / Stanford Intersection 1

Table 2: Level-of-Service Summary for 40th / Stanford Intersection without and with PAC 1

Table 3: 40th / Stanford Collision Manner History Summary: 2015 through 2022..... 7

Table 4: 40th / Stanford Collision Travel Direction Summary: 2015 through 2022 7

Table 5: 40th / Stanford Collision Injury Severity Total of 2015 through 2022..... 7

Table 6: Peak Traffic Hours at 40th / Stanford..... 10

Table 7: Monthly Factors..... 17

Table 8: Intersection Level-of-Service Criteria..... 39

Table 9: Level-of-Service – without Performing Arts Center – School Arrival and Departing Hours 39

Table 10: Level-of-Service –without and with PAC – 5:30 to 6:30 PM and 7:00 to 8:00 PM Hours 40

Table 11: Peak Hours Level-of-Service Summary for 40th / Stanford Intersection 40

Table 12: Level-of-Service Summary for 40th / Stanford Intersection without and with PAC 41

List of Appendices

Historic Collision Analysis A
2023 Traffic Counts..... B
2023 Traffic Counts Trip Distribution C
Level-of-Service D
 Summary..... D.1
 2023 Existing and Adjusted Traffic Volumes D.2
 2025 Ambient and Performing Arts Center Traffic Volumes D.3

Executive Summary

Introduction

The Phoenix Country Day School is planning to construct a new 600-seat Performing Arts Center (PAC) with an anticipated opening in 2025. All performances currently occurring at Dorrance Auditorium will occur at the Performing Arts Center in the future.

Results

The proposed Performing Arts Center is anticipated to generate 200 vehicles-per-hour prior to an event and 200 vehicles-per-hour subsequent to an event with non-student, non-faculty audiences.

Table 1 and **Table 2** summarize the intersection level-of-service results for 2023 and 2025, without and with the Performing Arts Center. The Phoenix Country Day School school-day is from 7:50 AM to 2:55 PM. The Performing Arts Center will only have events with friends-and-family audiences on school days after classes have ended and on weekends. Therefore, the only traffic generation from the Performing Arts Center is before and after an event. To be conservative, the time periods analyzed before and after an event were assumed to be earlier, when ambient traffic volumes are higher, than the events are likely to be scheduled.

Table 1: Peak Hours Level-of-Service Summary for 40th / Stanford Intersection

	7:15 to 8:15 AM PEAK HOUR			2:30 to 3:30 PM HOUR			3:30 to 4:30 PM HOUR		
	2023		2025	2023		2025	2023		2025
	EXISTING	ADJUSTED	AMBIENT	EXISTING	ADJUSTED	AMBIENT	EXISTING	ADJUSTED	AMBIENT
A	0	0	0	1	1	1	5	5	4
B	1	1	1	3	1	1	0	0	1
C	1	1	1	1	3	2	0	0	0
D	0	0	0	0	0	1	0	0	0
E	2	2	0	0	0	0	0	0	0
F	1	1	3	0	0	0	0	0	0
	5	5	5	5	5	5	5	5	5

Table 2: Level-of-Service Summary for 40th / Stanford Intersection without and with PAC

	5:30 to 6:30 PM HOUR				7:00 to 8:00 PM HOUR			
	2023		2025		2023		2025	
	EXISTING	ADJUSTED	AMBIENT	WITH PAC	EXISTING	ADJUSTED	AMBIENT	WITH PAC
A	5	5	5	5	5	5	5	5
B	0	0	0	0	0	0	0	0
C	0	0	0	0	0	0	0	0
D	0	0	0	0	0	0	0	0
E	0	0	0	0	0	0	0	0
F	0	0	0	0	0	0	0	0
	5	5	5	5	5	5	5	5

The 40th / Stanford roundabout has high traffic volumes and corresponding high delay during the school arrival time. During school dismissal time, the 40th / Stanford roundabout has lower traffic volumes and delay than the school arrival time, though higher traffic volume and delay than the remainder of the school day. The proposed Performing Arts Center will not have events during the school arrival and dismissal times, and therefore will not generate traffic at the 40th / Stanford intersection during the school arrival and dismissal times. The 40th / Stanford roundabout has low traffic volumes and corresponding low delay during all other hours of the day. Events with friends-and family-audiences will only occur on weekday late afternoons and evenings, and on weekends. During these times periods, the levels-of-service for all 40th / Stanford movements will be "A".

Recommendations without Performing Arts Center

No improvements to the street system are recommended. The existing delays at the 40th / Stanford roundabout are typical of schools and dissipate quickly after school arrival and dismissal periods.

Recommendations with Performing Arts Center

The Performing Arts Center will not affect school arrival and departure peak traffic periods. No street improvements are necessary or appropriate with the Performing Arts Center.

Introduction

The Phoenix Country Day School is planning to construct a new 600-seat Performing Arts Center (PAC) with an anticipated opening in 2025. All performances currently occurring at Dorrance Auditorium will occur at the Performing Arts Center in the future. The Phoenix Country Day School campus and general vicinity are depicted in **Figure 1**.




Figure 1: General Vicinity Aerial Photograph

Figure 2 provides the immediate vicinity of the Performing Arts Center and the existing Phoenix Country Day School. The four (4) existing parking areas are indicated in **Figure 2**. Access to the Phoenix Country Day School campus parking areas is provided to and from both 40th Street and Stanford Drive.




Figure 2: Immediate Vicinity Aerial Photograph

Scope of Study

Seven (7) purposes exist for this analysis:

- ❖ Evaluate existing traffic conditions.
- ❖ Evaluate recent historic traffic collisions.
- ❖ Estimate and evaluate future ambient 2025 traffic volumes.
- ❖ Estimate new traffic generated by new Performing Arts Center.
- ❖ Distribute and assign new traffic to the adjacent intersection of 40th Street and Stanford Drive.
- ❖ Evaluate year 2025 traffic conditions with new Performing Arts Center.
- ❖ Determine need for modified traffic control.

The one (1) existing study intersection is:

1. 40th Street and Stanford Drive

Surrounding Transportation System

Figure 3 provides a street map, intersection traffic control, and intersection lane configurations in the immediate vicinity.




Figure 3: Intersection Existing Lane Configurations

Figure 4 provides a schematic of the proposed Performing Arts Center site plan for the existing Phoenix Country Day School.




Figure 4: Phoenix Country Day School Performing Arts Center Site Plan

The existing Phoenix Country Day School has three (3) accesses with Stanford Drive and four (4) accesses with 40th Street. No changes to these seven (7) accesses are proposed. No changes to the on-site circulation are proposed.

Collision Analysis

The historic collision experience for the study intersection of 40th Street and Stanford Drive were analyzed. The collision data for calendar years 2015 through 2022. The summary data provided by the Arizona Department of Transportation does not provide travel direction and injury severity for every collision.

Appendix A provides the complete collision data. **Table 3**, **Table 4**, and **Table 5** respectively provide the collision manner and travel direction summaries for all years. Not all collision report summaries include travel directions. The manner of collision and the travel directions of involved vehicles with a higher portion of total collisions are highlighted in black.

Table 3: 40th / Stanford Collision Manner History Summary: 2015 through 2022

	REAR-END	ANGLE	LEFT-TURN ANGLE	LEFT-TURN HEAD-ON	SIDE-SWIPE SAME	SIDE-SWIPE OPPOSITE	HEAD-ON	SINGLE VEHICLE	OTHER	TOTAL
2015	0	0	0	0	0	0	0	1	0	1
2016	0	2	0	0	0	0	0	1	0	3
2017	0	1	0	0	0	0	0	4	0	5
2018	0	1	0	0	1	0	0	0	0	2
2019	0	0	0	0	0	0	0	0	0	0
2020	1	1	0	0	1	0	0	2	1	6
2021	2	1	0	0	0	0	0	1	0	4
2022	0	1	0	0	0	0	0	0	0	1
TOTAL	3	7	0	0	2	0	0	9	1	22
PORTION	14%	32%	0%	0%	9%	0%	0%	41%	5%	100%

Table 4: 40th / Stanford Collision Travel Direction Summary: 2015 through 2022

	2015	2016	2017	2018	2019	2020	2021	2022	TOTAL	PORTION
Northbound Only	0	0	1	0	0	1	0	0	2	11%
Southbound Only	0	0	0	0	0	0	1	0	1	5%
Eastbound Only	0	0	1	0	0	1	0	0	2	11%
Westbound Only	0	1	1	0	0	0	0	0	2	11%
Northbound and Northbound	0	0	0	0	0	2	2	0	4	21%
Southbound and Southbound	0	0	0	0	0	0	0	0	0	0%
Eastbound and Eastbound	0	0	0	0	0	0	0	1	1	5%
Westbound and Westbound	0	0	0	0	0	0	0	0	0	0%
Northbound and Eastbound	0	1	0	0	0	1	0	0	2	11%
Northbound and Westbound	0	0	0	1	0	0	0	0	1	5%
Southbound and Eastbound	0	0	0	0	0	1	0	0	1	5%
Southbound and Westbound	0	0	1	1	0	0	1	0	3	16%
Northbound and Southbound	0	0	0	0	0	0	0	0	0	0%
Eastbound and Westbound	0	0	0	0	0	0	0	0	0	0%
TOTAL	0	2	4	2	0	6	4	1	19	100%

Table 5: 40th / Stanford Collision Injury Severity Total of 2015 through 2022

SEVERITY	NUMBER	PORTION
No Injury	18	86%
Possible Injury	1	5%
Suspected Minor Injury	2	10%
Suspected Serious Injury	0	0%
Fatal Injury	0	0%
Unknown	0	0%
Not Reported	0	0%
TOTAL	21	100%

Collisions are irregular and infrequent events. Over the past eight (8) years, the average number of collisions per year at the 40th / Stanford intersection was 2.75, varying from a high of six (6) in 2020 and a low of zero (0) in 2019. The roundabout was constructed between February 2013 and January 2015, so all the provided collision data is with the roundabout.

There were no fatal or suspected serious injuries, which is typical for roundabouts.

The dominant collision type is single-vehicle, which is unusual, involving nine (9) of the 22 collisions. There were seven (7) angle collisions (one vehicle on 40th Street and the other vehicle on Stanford Drive) over the eight (8) years, three (3) rear-end, two (2) side-swipe-same-direction, and one (1) other.

Of the single-vehicle collisions, one (1) occurred in 2015, and the ADOT collision summaries lists most characteristics as unknown. One (1) occurred in 2016, and involved a westbound truck on 8/16 at 11:25 AM, with no citations indicated. In 2017, four (4) single-vehicle collisions occurred, one each were listed as unknown, eastbound, westbound, and northbound. In one collision, the driver of one vehicle was cited for both Speed Too Fast For Conditions and Failure to Keep in Proper Lane. In one collision, one driver was cited for Failure to Keep in Proper Lane. In another collision, one driver was cited for Speed Too Fast for Conditions.

No single-vehicle collisions occurred at 40th / Stanford in either 2018 or 2019. In 2020, two (2) single-vehicle collisions occurred: one (1) involved an eastbound vehicle with the driver cited for Failure to Keep in Proper Lane, and one (1) involved a northbound vehicle with the driver cited for Speed Too Fast for Conditions. One (1) single-vehicle collision occurred in 2021, which involved a southbound vehicle with the driver cited for Made Improper Turn. No single-vehicle collisions occurred at the 40th / Stanford intersection in 2022.

There are no patterns of collision manner or travel direction. Therefore, no mitigation is necessary or appropriate. While all collisions should be prevented, the primary collision cause is poor driver behavior. The recommendation is that no changes of the intersection design or operation should occur.

Existing Traffic Volumes

Traffic counts were obtained on 29 August 2023. **Appendix B** provides the turning movement counts for 24 hours in 15-minute increments for the study intersection. **Figure 5** provides a graph of the hourly volumes for each hour for 24 hours.

Figure 6 provides the hourly volumes for every 15-minute period from 6:00 AM through 7:30 PM. The Phoenix Country Day School day begins at 7:50 AM and ends at 2:55 PM.




Figure 5: 24 Hour Counts at 40th / Stanford




Figure 6: 6:00 AM to 7:30 PM 60-Minute Counts at 40th / Stanford with Analyzed Hours Indicated

Table 6: Peak Traffic Hours at 40th / Stanford

Table 6 provides the three (3) highest hourly volumes with their respective time-period. Table 6 also provides two additional hours and their respective hourly volumes. These additional hours are assumed to be the arrival and departure times of events at the proposed Performing Arts Center. These hours are earlier than are anticipated. However, they were selected for analysis to ensure a conservative analysis.

TIME PERIOD		TOTAL VOLUME
7:15 AM to 8:15 AM	Highest	1,103
2:30 PM to 3:30 PM	2 nd Highest	917
4:30 PM to 5:30 PM	3 rd Highest	862
5:30 PM to 6:30 PM	Additional	603
7:00 PM to 8:00 PM	Additional	329

Later hours, closer to the actual beginning and ending of events, would have lower ambient traffic volumes at 40th Street and Stanford Drive.

Figure 7 through Figure 15 provide the existing 2023 day approach and departure volumes, and the approach and departure, and turning movement volumes for the five (5) analyzed hours.




Figure 7: Existing 2023 Day Approach and Departure Volumes




Figure 8: Existing 2023 7:15 to 8:15 AM Peak Hour Approach and Departure Volumes




Figure 9: Existing 2023 7:15 to 8:15 AM Peak Hour Turning Movement Volumes




Figure 10: Existing 2023 2:30 to 3:30 PM Peak Hour Approach and Departure Volumes




Figure 11: Existing 2023 2:30 to 3:30 PM Peak Hour Turning Volumes




Figure 12: Existing 2023 4:30 to 5:30 PM Peak Hour Approach and Departure Volumes




Figure 13: Existing 2023 4:30 to 5:30 PM Peak Hour Turning Volumes




Figure 14: Existing 2023 5:30 to 6:30 PM Peak Hour Approach and Departure Volumes




Figure 15: Existing 2023 5:30 to 6:30 PM Peak Hour Turning Volumes




Figure 16: Existing 2023 7:00 to 8:00 PM Peak Hour Approach and Departure Volumes




Figure 17: Existing 2023 7:00 to 8:00 PM Peak Hour Turning Volumes

Because traffic counts vary from month-to-month, often monthly factors are utilized to adjust a specific count month to an average for the year. Monthly factors were developed by the Maricopa Association of Governments in 2007.

Table 7 provides these monthly factors. These factors indicate that counts in January, September, and October are the closest to typical. Counts in August are 97.5% of typical.

The traffic counts occurred on 29 August; and therefore, each turning movement count was divided by 0.975 to represent the typical weekday traffic volume for the entire year.

Figure 18 through **Figure 28** provide the adjusted 2023 day approach and departure, the peak hour approach and departure volumes, and turning movement volumes for the five (5) study hours.

Table 7: Monthly Factors

	Factor
January	1.003
February	1.045
March	1.040
April	1.044
May	1.022
June	0.972
July	0.930
August	0.975
September	0.995
October	0.994
November	1.008
December	0.974




Figure 18: Adjusted 2023 Day Approach and Departure Volumes




Figure 19: Adjusted 2023 7:15 to 8:15 AM Peak Hour Approach and Departure Volumes




Figure 20: Adjusted 2023 7:15 to 8:15 AM Peak Hour Turning Movement Volumes




Figure 21: Adjusted 2023 2:30 to 3:30 PM Peak Hour Approach and Departure Volumes




Figure 22: Adjusted 2023 2:30 to 3:30 PM Peak Hour Turning Volumes




Figure 23: Adjusted 2023 4:30 to 5:30 PM Peak Hour Approach and Departure Volumes




Figure 24: Adjusted 2023 4:30 to 5:30 PM Peak Hour Turning Volumes




Figure 25: Adjusted 2023 5:30 to 6:30 PM Peak Hour Approach and Departure Volumes




Figure 26: Adjusted 2023 5:30 to 6:30 PM Peak Hour Turning Volumes




Figure 27: Adjusted 2023 7:00 to 8:00 PM Peak Hour Approach and Departure Volumes




Figure 28: Adjusted 2023 7:00 to 8:00 PM Peak Hour Turning Volumes

Future Ambient 2025

To determine the future 2025 traffic volumes, the City of Scottsdale publication “Traffic Volume and Collision Report” was consulted. The City of Scottsdale publishes this document for every even-numbered year. The 2022 edition was published in September 2023. The total vehicles-miles-travelled on the major street segments in Scottsdale, as stated on page 1 of the report, decreased from 2020 at 3.81 to 3.78 in 2022. This is a 0.79% decrease in two (2) years. Pages 96 to 104 of the 2022 City of Scottsdale Traffic Volume and Collision Report individually lists 323 segments, their 2022 volume, their 2020 volume, and their percent change from 2020 to 2022. The average two-year change was – 1.18%.

Additionally, 40th Street, north of Camelback Road, is a residential street extending approximately 0.65 mile north of Stanford Drive. Stanford Drive is also a residential collector street serving exclusively large-lot residential neighborhoods. It only extends from 32nd Street to 44th Street, 1.5 miles. The properties that are served by both streets are completely built. Therefore, minimal traffic-generating developments are anticipated on the properties served by both 40th Street and Stanford Drive.

To remain conservatively large, to determine the future 2025 traffic volumes at the 40th / Stanford intersection, a 2% linear increase was applied to each Adjusted 2023 approach volume, and the turning movement volumes were determined by the same ratio as the Adjusted 2023 volumes. The 2025 approach volumes and turning movement volumes were approximately to the nearest 10 vehicles-per-hour and to a minimum volume of 10 vehicles-per-hour.

Figure 29 through Figure 39 provide the ambient 2025 traffic volumes.




Figure 29: Ambient 2025 Day Approach and Departure Volumes




Figure 30: Ambient 2025 7:15 to 8:15 AM Peak Hour Approach and Departure Volumes




Figure 31: Ambient 2025 7:15 to 8:15 AM Peak Hour Turning Movement Volumes




Figure 32: Ambient 2025 2:30 to 3:30 PM Peak Hour Approach and Departure Volumes




Figure 33: Ambient 2025 2:30 to 3:30 PM Peak Hour Turning Volumes




Figure 34: Ambient 2025 4:30 to 5:30 PM Peak Hour Approach and Departure Volumes




Figure 35: Ambient 2025 4:30 to 5:30 PM Peak Hour Turning Volumes




Figure 36: Ambient 2025 5:30 to 6:30 PM Peak Hour Approach and Departure Volumes




Figure 37: Ambient 2025 5:30 to 6:30 PM Peak Hour Turning Volumes




Figure 38: Ambient 2025 7:00 to 8:00 PM Peak Hour Approach and Departure Volumes




Figure 39: Ambient 2025 7:00 to 8:00 PM Peak Hour Turning Volumes

Planned Events at Performing Arts Center

Listed below are the only family-and-friends events scheduled for the new Performing Arts Center. All other events at the Performing Arts Center will be during the school day with only students, faculty, and employees in attendance.

Parent Back to School	September	Weeknight	5:30 to 7:30 PM
Upper School Fall Play	October or November	Friday and Saturday	7:00 to 9:00 PM
Student Concerts	November	2 or 3 Weeknights	7:00 to 9:00 PM
Middle School Play	December	Friday	7:00 to 9:00 PM
Middle School Concerts	December	Weeknight	7:00 to 9:00 PM
Upper School Musical	March	Friday and Saturday	7:00 to 9:00 PM
Upper School Musical	March	Sunday	2:00 to 5:00 PM
Maverick Series Speaker	February	Weeknight	7:00 to 9:00 PM
Middle School Musical	April	Friday	7:00 to 9:00 PM
Student Concerts	April 3	Weeknights	7:00 to 9:00 PM
Arts Walk and One-Act Plays ...	May	Weeknights	5:00 to 9:00 PM

Proposed Performing Arts Center Estimated Trip Generation

Typically trip generation for proposed developments is estimated with the procedures and data contained within the Institute of Transportation Engineers *Trip Generation Manual, 11th Edition*, published in 2021. This document provides traffic volume data from existing developments throughout the United States and Canada, from 1980 through 2019, that can be utilized to estimate trips from proposed developments. The traffic data are provided for 179 land use categories separated into 10 major land use categories. The estimated traffic volume is dependent upon independent variables defined by the characteristics and size of each land use category. Data are typically provided for five (5) weekday time periods and four (4) weekend time periods.

However, a category for performance venues is not included in the *Trip Generation Manual*. Therefore, this methodology cannot be used. It is logical to utilize the Town of Paradise Valley parking guidelines, which suggest one (1) parking space for every three (3) seats. Thereby, the 600-seat Performing Arts Center (PAC) would generate 200 vehicles-per-hour entering and 200 vehicles-per-hour exiting. The entering traffic was assumed to arrive between 5:30 and 6:30 PM. This time period is likely earlier than Performing Arts Center traffic would arrive. However, this traffic volume is higher than later hours, and therefore is conservative. Similarly, the exiting traffic was assumed to depart between 7:00 and 8:00 PM. This time period is likely earlier than Performing Arts Center traffic would depart. However, this traffic volume is higher than later hours, and therefore is conservative.

Figure 40 provides an aerial photograph of the portions of Paradise Valley in the greater vicinity of the Phoenix Country Day School campus. **Figure 41** provides a street schematic of the portions of Paradise Valley in the greater vicinity of the Phoenix Country Day School campus. These two (2) figures reveal that Stanford Drive, east of 40th Street, provides access to more of Paradise Valley than does 40th Street, north of Stanford Drive. Stanford Drive connects with 44th Street, which becomes McDonald Drive, then Tatum Boulevard, which connects to Lincoln Drive, while 40th Street does not connect to Lincoln Drive. This street access is an important consideration for determining the trip distribution of the traffic approaching and departing from the Performing Arts Center of the Phoenix Country Day School. Therefore, more traffic will utilize Stanford Drive, east of 40th Street, than 40th Street, north of Stanford Drive.



Figure 40: Aerial Photograph of Greater Vicinity of Phoenix Country Day School




Figure 41: Street Schematic of Greater Vicinity of Phoenix Country Day School

The final page of **Appendix B** provides the existing 2023 traffic count directional distribution for both approaching and departing traffic. These percentages were utilized to determine the travel directions of the vehicles arriving and departing family-and-friends events at the Performing Arts Center.

The Performing Arts Center is estimated to generate 200 hourly vehicles arriving for a friends-and-family event. As indicated in the previous list of scheduled Performing Arts Center events, ten (10) of the events are scheduled for weeknights; of which eight (8) are anticipated to occur from 7:00 to 9:00 PM. The remaining two (2) weeknight events begin at 5:00 or 5:30 PM. The event arrival hour was conservatively assumed to be 5:30 to 6:30 PM. As indicated in the existing trip distribution on the final page of **Appendix B**, this is the peak traffic volume hour after the school day. As indicated in **Figure 5** and **Figure 6**, after 6:30 PM, the ambient traffic volumes decrease substantially. Therefore, the actual event arrival period ambient traffic volumes will be much lower.

In accordance with the distribution of existing traffic volumes, of this arriving PAC traffic, 28% was assumed to arrive from Stanford Drive east of 40th Street, and 23% from Stanford Drive west of 40th Street. Of the arriving PAC traffic, 7% of the traffic was assumed to arrive from 40th Street north of Stanford Drive, and 42% of the traffic was assumed to arrive from 40th Street south of Stanford Drive. The 23% of the traffic arriving from Stanford Drive, west of 40th Street, will utilize the Phoenix Country Day School accesses, and

therefore will not utilize the 40th / Stanford roundabout. All Performing Arts Center traffic was assumed to utilize the Stanford Drive accesses. This is conservative, as some traffic will utilize the 40th Street accesses. The Performing Arts Center is also estimated to generate 200 hourly vehicles departing from a friends-and-family event. As indicated in the previous list of scheduled Performing Arts Center events, ten (10) of the events are scheduled for weeknights; of which nine (9) are anticipated to end at 9:00 PM. The remaining weeknight event ends at 7:30 PM. The event departure hour was conservatively assumed to be 7:00 to 8:00 PM. As indicated in the existing trip distribution on the final page of **Appendix B**, this is the peak traffic volume hour after the school day. As indicated in **Figure 5** and **Figure 6**, after 8:00 PM, the ambient traffic volumes decrease substantially. Therefore, the actual event departure period ambient traffic volumes will be much lower.

In accordance with the distribution of existing traffic volumes, of this departing PAC traffic, 29% was assumed to depart on Stanford Drive, east of 40th Street, and 28% from Stanford Drive, west of 40th Street. Of the departing PAC traffic, 17% of the traffic was assumed to depart on 40th Street, north of Stanford Drive, and 26% of the traffic was assumed to depart on 40th Street, south of Stanford Drive. The 28% of the traffic departing on Stanford Drive, west of 40th Street, will utilize the Phoenix Country Day School accesses, and therefore will not utilize the 40th / Stanford roundabout. All Performing Arts Center traffic was assumed to utilize the Stanford Drive accesses. This is conservative, as some traffic will utilize the 40th Street accesses.

The Performing Arts Center daily traffic is the sum of the hourly entering traffic from 5:30 to 6:30 PM and the hourly exiting traffic from 7:00 to 8:00 PM. The Performing Arts Center will not generate traffic other than the event-arrival hour and the event-departure hour.

The resulting Performing Arts Center traffic daily approach and departure, and hourly turning movements at the 40th / Stanford intersection are provided in **Figure 42** through **Figure 46** respectively.




Figure 42: PCDS Performing Arts Center Day Approach and Departure Volumes




Figure 43: PCDS PAC 5:30 to 6:30 PM Peak Hour Approach and Departure Volumes




Figure 44: PCDS Performing Arts Center 5:30 to 6:30 PM Peak Hour Turning Movement Volumes




Figure 45: PCDS PAC 7:00 to 8:00 PM Peak Hour Approach and Departure Volumes




Figure 46: PCDS Performing Arts Center 7:00 to 8:00 PM Peak Hour Turning Movement Volumes

Figure 47 through Figure 51 respectively provide the 2025 with the new Performing Arts Center day, 5:30 to 6:30 PM, and 7:00 to 8:00 PM peak hours traffic volume.




Figure 47: 2025 with PCDS Performing Arts Center Day Approach and Departure Volumes




Figure 48: 2025 with PCDS PAC 5:30 to 6:30 PM Peak Hour Approach and Departure Volumes




Figure 49: 2025 with PCDS Performing Arts Center 5:30 to 6:30 PM Peak Hour Turning Volumes




Figure 50: 2025 with PCDS PAC 7:00 to 8:00 PM Peak Hour Approach and Departure Volumes




Figure 51: 2025 with PCDS Performing Arts Center 7:00 to 8:00 PM Peak Hour Turning Volumes

Figure 52 provides the traffic volumes entering and exiting the Phoenix Country Day School, arriving to and departing from Performing Arts Center events. Also provided are the estimated 2025 hourly traffic volumes on Stanford Drive. The parking areas directly accessible from Stanford Drive contain 227 parking spaces – adequate for the anticipated 200 vehicles. Another 229 parking spaces will be available directly accessible from 40th Street, which will likely also be utilized. The Performing Arts Center traffic volumes indicated in Figure 52 assume that all event traffic will utilize the Stanford Drive access, which is conservative.





Figure 52: 2025 with PCDS Performing Arts Center Traffic Volume – School Access

Level-of-Service Analysis

The ability of a transportation system to transmit the transportation demand is characterized as its level-of-service (LOS). Level-of-service is a rating system from “A” representing the most preferred operation to “F” representing the least preferred operation. Typically, levels-of-service “C” and “D” provide an optimal balance between traffic operation and street system expenditures.

The appropriate reference for level-of-service analysis and calculation is the *Highway Capacity Manual*, published by the Transportation Research Board. This manual considers average delay as the measure to determine level-of-service at intersections. For signalized intersections and multi-way stop intersections, the delay and level-of-service are calculated for the entire intersection, each approach, and each turning movement. For two-way intersections, the delay and level-of-service are determined only for each stopped approach and for left-turns from the uncontrolled approach. **Table 8:** provides a diagram depicting level-of-service and delay criteria for intersections.

Table 8: Intersection Level-of-Service Criteria



The Synchro *Highway Capacity Manual* methodology was utilized for these analyses. The detailed results of these analyses are provided in **Appendix D**. **Appendix D** includes a comparison of the different conditions by time period, with highlighted cells that indicate when a level-of-service changes. **Table 9** summarizes the three (3) time periods that are not affected by the Performing Arts Center. **Table 10** summarizes the two (2) time periods that are affected by the Performing Arts Center. The numbers indicate the number of approaches and intersection that experience the designated level-of-service.

Table 9: Level-of-Service – without Performing Arts Center – School Arrival and Departing Hours

	7:15 to 8:15 AM PEAK HOUR			2:30 to 3:30 PM HOUR			3:30 to 4:30 PM HOUR		
	2023		2025	2023		2025	2023		2025
	EXISTING	ADJUSTED	AMBIENT	EXISTING	ADJUSTED	AMBIENT	EXISTING	ADJUSTED	AMBIENT
A	0	0	0	1	1	1	5	5	4
B	1	1	1	3	1	1	0	0	1
C	1	1	1	1	3	2	0	0	0
D	0	0	0	0	0	1	0	0	0
E	2	2	0	0	0	0	0	0	0
F	1	1	3	0	0	0	0	0	0
	5	5	5	5	5	5	5	5	5

Table 10: Level-of-Service –without and with PAC – 5:30 to 6:30 PM and 7:00 to 8:00 PM Hours

	5:30 to 6:30 PM HOUR				7:00 to 8:00 PM HOUR			
	2023		2025		2023		2025	
	EXISTING	ADJUSTED	AMBIENT	WITH PAC	EXISTING	ADJUSTED	AMBIENT	WITH PAC
A	5	5	5	5	5	5	5	5
B	0	0	0	0	0	0	0	0
C	0	0	0	0	0	0	0	0
D	0	0	0	0	0	0	0	0
E	0	0	0	0	0	0	0	0
F	0	0	0	0	0	0	0	0
	5	5	5	5	5	5	5	5

Results

The proposed Performing Arts Center is anticipated to generate 200 vehicles-per-hour prior to an event and 200 vehicles-per-hour subsequent to an event with friends-and-family audiences.

Table 11 and **Table 12** summarize the intersection level-of-service results for 2023 and 2025, without and with the Performing Arts Center. The Performing Arts Center will only have events with friends-and-family audiences on school days after classes have ended and on weekends. Therefore, the only traffic generation from the Performing Arts Center is before and after an event. To be conservative, the time periods analyzed before and after an event were assumed to be earlier, when ambient traffic volumes are higher, than the events are likely to be scheduled.

Table 11: Peak Hours Level-of-Service Summary for 40th / Stanford Intersection

	7:15 to 8:15 AM PEAK HOUR			2:30 to 3:30 PM HOUR			3:30 to 4:30 PM HOUR		
	2023		2025	2023		2025	2023		2025
	EXISTING	ADJUSTED	AMBIENT	EXISTING	ADJUSTED	AMBIENT	EXISTING	ADJUSTED	AMBIENT
A	0	0	0	1	1	1	5	5	4
B	1	1	1	3	1	1	0	0	1
C	1	1	1	1	3	2	0	0	0
D	0	0	0	0	0	1	0	0	0
E	2	2	0	0	0	0	0	0	0
F	1	1	3	0	0	0	0	0	0
	5	5	5	5	5	5	5	5	5

Table 12: Level-of-Service Summary for 40th / Stanford Intersection without and with PAC

	5:30 to 6:30 PM HOUR				7:00 to 8:00 PM HOUR			
	2023		2025		2023		2025	
	EXISTING	ADJUSTED	AMBIENT	WITH PAC	EXISTING	ADJUSTED	AMBIENT	WITH PAC
A	5	5	5	5	5	5	5	5
B	0	0	0	0	0	0	0	0
C	0	0	0	0	0	0	0	0
D	0	0	0	0	0	0	0	0
E	0	0	0	0	0	0	0	0
F	0	0	0	0	0	0	0	0
	5	5	5	5	5	5	5	5

Conclusions

The 40th / Stanford roundabout has high traffic volumes and corresponding high delay during the school arrival time. During school dismissal time, the 40th / Stanford roundabout has lower traffic volumes and delay than the school arrival time, though higher traffic volume and delay than the remainder of the school day. The proposed Performing Arts Center will not have events during the school arrival and dismissal times, and therefore will not generate traffic at the 40th / Stanford intersection during the school arrival and dismissal times. The 40th / Stanford roundabout has low traffic volumes and corresponding low delay during all other hours of the day. Events with friends-and family-audiences will only occur on weekday late afternoons and evenings, and on weekends. During these times periods the levels-of-service for all 40th / Stanford movements will be “A”.

Recommendations without Performing Arts Center

No improvements to the street system are recommended. The existing delay at the 40th / Stanford roundabout are typical of schools and dissipate quickly after school arrival and dismissal periods.

Recommendations with Performing Arts Center

The Performing Arts Center will not affect school arrival and dismissal peak traffic periods. No street improvements are necessary or appropriate with the Performing Arts Center.

Appendix A
Collision Analysis



40th Street & Stanford Drive - 2015

INCIDENT ID	LATITUDE	LONGITUDE	DATE	TIME	COLLISION MANNER	INJURY SEVERITY	TRAVEL DIRECTION	ACTION	VEHICLE	CONTROL	DISTRACTION	FIRST VIOLATION	SECOND VIOLATION
3012866	33.5173	-111.9952	10 / 16	1:40 PM	Single Vehicle	No Injury	Unknown	Unknown	Not Reported	Yield Signs	Unknown	Unknown	

40th Street & Stanford Drive - 2016

INCIDENT ID	LATITUDE	LONGITUDE	DATE	TIME	COLLISION MANNER	INJURY SEVERITY	TRAVEL DIRECTION	ACTION	VEHICLE	CONTROL	DISTRACTION	FIRST VIOLATION	SECOND VIOLATION
3096873 3096873	33.5173	-111.9952	05 / 27	8:37 AM	Angle	Suspected Minor Injury	Northbound Eastbound	Other Straight	Car Pedalcyclist	Yield Signs Yield Signs	Unknown Unknown	Failed to Yield Right of Way No Improper Action	
3114838 3114838	33.5173	-111.9952	07 / 31	10:51 AM	Angle	Possible Injury	Unknown Unknown	Straight Straight	Pick-up Truck Car	Unknown Unknown	Unknown Unknown	Failed to Yield Right of Way Unknown	
3129552	33.5173	-111.9952	08 / 16	11:25 AM	Single Vehicle	No Injury	Westbound	Unknown	Truck	No Controls	Unknown	Unknown	

40th Street & Stanford Drive - 2017

INCIDENT ID	LATITUDE	LONGITUDE	DATE	TIME	COLLISION MANNER	INJURY SEVERITY	TRAVEL DIRECTION	ACTION	VEHICLE	CONTROL	DISTRACTION	FIRST VIOLATION	SECOND VIOLATION
3211363 3211363	33.5173	-111.9952	01 / 02	10:45 PM	Angle	No Injury	Southbound Westbound	Straight Straight	Car Car	Yield Signs Yield Signs	Unknown Unknown	Failed to Yield Right of Way No Improper Action	
3223907	33.5173	-111.9952	03 / 05	4:22 AM	Single Vehicle	No Injury	Eastbound	Straight	Car	Yield Signs	Unknown	Speed Too Fast For Conditions	Failed to Keep in Proper Lane
3256382	33.5173	-111.9952	07 / 06	1:40 AM	Single Vehicle	No Injury	Unknown	Unknown	Not Reported	Yield Signs	Unknown	Unknown	
3298563	33.5173	-111.9952	11 / 25	7:37 AM	Single Vehicle	No Injury	Northbound	Straight	Truck	Yield Signs	Not Distracted	Speed Too Fast For Conditions	
3312980	33.5173	-111.9952	12 / 21	7:32 AM	Single Vehicle	No Injury	Westbound	Unknown	Not Reported	No Controls	Unknown	Failed to Keep in Proper Lane	

40th Street & Stanford Drive - 2018

INCIDENT ID	LATITUDE	LONGITUDE	DATE	TIME	COLLISION MANNER	INJURY SEVERITY	TRAVEL DIRECTION	ACTION	VEHICLE	CONTROL	DISTRACTION	FIRST VIOLATION	SECOND VIOLATION
3627119 3627119	33.5173	-111.9952	01 / 13	3:24 PM	Angle	No Injury	Westbound Northbound	Turning Right Turning Left	Car Car	Yield Signs Yield Signs	Not Distracted Not Distracted	Disregarded Traffic Signal No Improper Action	
3627630 3627630	33.5173	-111.9952	08 / 23	3:05 PM	Sideswipe Same Direction	No Injury	Southbound Westbound	Slowing Slowing	Car Car	Yield Signs Yield Signs	Unknown Distracted	Unknown Unknown	

40th Street & Stanford Drive - 2020

INCIDENT ID	LATITUDE	LONGITUDE	DATE	TIME	COLLISION MANNER	INJURY SEVERITY	TRAVEL		VEHICLE	CONTROL	DISTRACTION	FIRST VIOLATION	SECOND VIOLATION
							DIRECTION	ACTION					
3670759	33.5173	-111.9971	05 / 04	3:22 AM	Single Vehicle	No Injury	Eastbound	Unknown	Car	No Controls	Unknown	Failed to Keep in Proper Lane	
3699265 3699265	33.5173	-111.9952	07 / 15	3:49 PM	Sideswipe Same Direction	No Injury	Eastbound Southbound	Straight Straight	Car Car	No Controls No Controls	Unknown Not Distracted	Failed to Yield Right of Way No Improper Action	
3699270	33.5173	-111.9952	07 / 30	6:27 AM	Single Vehicle	No Injury	Northbound	Straight	Unknown	No Controls	Unknown	Speed Too Fast For Conditions	
3699274 3699274	33.5173	-111.9952	08 / 12	9:15 AM	Other	No Injury	Northbound Northbound	Backing Stopped	Car Car	No Controls No Controls	Not Distracted Not Distracted	Other No Improper Action	
3719677 3719677	33.5171	-111.9953	10 / 19	7:34 AM	Rear End	No Injury	Northbound Northbound	Straight Slowing	Pick-up Truck Car	No Controls No Controls	Unknown Not Distracted	Speed Too Fast For Conditions No Improper Action	
3719681 3719681	33.5173	-111.9952	10 / 31	11:27 AM	Angle	Suspected Minor Injury	Northbound Eastbound	Straight Straight	Car Pedalcyclist	Yield Sign No Controls	Not Distracted Not Distracted	Failed to Yield Right of Way No Improper Action	

40th Street & Stanford Drive - 2021

INCIDENT ID	LATITUDE	LONGITUDE	DATE	TIME	COLLISION MANNER	INJURY SEVERITY	TRAVEL		VEHICLE	CONTROL	DISTRACTION	FIRST VIOLATION	SECOND VIOLATION
							DIRECTION	ACTION					
3751539 3751539	33.5171	-111.9953	04 / 08	8:11 AM	Rear End	No Injury	Northbound Northbound	Straight Stopped	Car Car	No Controls Yield Signs	Not Distracted Not Distracted	Speed Too Fast For Conditions No Improper Action	
3804165 3804165	33.5159	-111.9953	02 / 05	11:30 AM	Rear End	No Injury	Northbound Northbound	Straight Stopped	Car Car	No Controls No Controls	Distracted Unknow Not Distracted	Followed Too Closely No Improper Action	
3812235	33.5173	-111.9952	05 / 10	8:00 AM	Single Vehicle	No Injury	Southbound	Turning Left	Truck	Roundabout	Unknown	Made Improper Turn	
3859615 3859615	33.5173	-111.9952	12 / 05	4:42 PM	Angle	No Injury	Southbound Westbound	Straight Straight	Car Car	Roundabout Roundabout	Not Distracted Not Distracted	Disregarded Traffic Signal No Improper Action	

40th Street & Stanford Drive - 2022


INCIDENT ID	LATITUDE	LONGITUDE	DATE	TIME	COLLISION MANNER	INJURY SEVERITY	TRAVEL		VEHICLE	CONTROL	DISTRACTION	FIRST VIOLATION	SECOND VIOLATION
							DIRECTION	ACTION					
3897540 3897540	33.5173	-111.9952	02 / 09	9:39 AM	Angle	No Injury	Eastbound Eastbound	Turning Right Straight	Truck Car	Roundabout Roundabout	Unknown Not Distracted	Failed to Yield Right of Way No Improper Action	

Appendix B

2023 Traffic Counts



PCDS PAC
40th STREET and STANFORD DRIVE - TUESDAY - 8/29/2023



PCDS PAC

40th STREET and STANFORD DRIVE - TUESDAY - 8/29/2023

EXISTING 5:00 AM to 10:00 AM



BEGIN TIME	STANFORD DRIVE EASTBOUND				STANFORD DRIVE WESTBOUND				40th STREET NORTHBOUND				40th STREET SOUTHBOUND				ALL TOTAL	60 MINUTE TOTAL
	LEFT	THRU	RIGHT	TOTAL	LEFT	THRU	RIGHT	TOTAL	LEFT	THRU	RIGHT	TOTAL	LEFT	THRU	RIGHT	TOTAL		
5:00 AM	0	4	3	7	4	1	0	5	7	4	1	12	1	4	0	5	29	150
5:15 AM	1	8	10	19	5	4	0	9	10	3	3	16	1	2	0	3	47	166
5:30 AM	0	4	3	7	4	3	0	7	4	0	3	7	0	2	0	2	23	164
5:45 AM	0	8	4	12	9	6	0	15	7	3	4	14	2	8	0	10	51	211
6:00 AM	1	5	9	15	4	4	2	10	3	8	3	14	2	3	1	6	45	245
6:15 AM	3	7	3	13	4	8	4	16	8	0	1	9	2	3	2	7	45	299
6:30 AM	0	8	9	17	7	3	1	11	8	11	13	32	3	6	1	10	70	479
6:45 AM	2	14	17	33	9	12	1	22	12	4	8	24	2	3	1	6	85	890
7:00 AM	0	11	12	23	7	16	1	24	13	5	7	25	4	19	4	27	99	1,066
7:15 AM	0	32	34	66	37	49	2	88	29	7	15	51	4	14	2	20	225	1,103
7:30 AM	2	66	73	141	106	105	0	211	48	12	32	92	2	23	12	37	481	1,017
7:45 AM	2	58	48	108	35	36	6	77	20	10	23	53	4	14	5	23	261	694
8:00 AM	3	13	22	38	23	14	2	39	6	15	22	43	3	12	1	16	136	585
8:15 AM	3	14	26	43	25	13	7	45	12	11	12	35	5	11	0	16	139	571
8:30 AM	2	18	36	56	28	18	4	50	5	14	17	36	3	12	1	16	158	535
8:45 AM	2	24	21	47	16	20	2	38	19	15	11	45	2	15	5	22	152	474
9:00 AM	3	24	24	51	12	13	3	28	7	6	18	31	0	8	4	12	122	428
9:15 AM	3	17	19	39	7	11	2	20	9	9	8	26	2	13	3	18	103	413
9:30 AM	1	16	20	37	12	8	0	20	6	15	9	30	1	9	0	10	97	397
9:45 AM	2	11	22	35	8	14	6	28	9	16	8	33	0	7	3	10	106	423
AM PEAK	7	169	177	353	201	204	10	415	103	44	92	239	13	63	20	96	1,103	1,103
PHF	0.58	0.64	0.61	0.63	0.47	0.49	0.42	0.49	0.54	0.73	0.72	0.49	0.81	0.68	0.42	0.65		

PCDS PAC

40th STREET and STANFORD DRIVE - TUESDAY - 8/29/2023



EXISTING 10:00 AM to 3:00 PM

BEGIN TIME	STANFORD DRIVE EASTBOUND				STANFORD DRIVE WESTBOUND				40th STREET NORTHBOUND				40th STREET SOUTHBOUND				ALL TOTAL	60 MIN. TOTAL
	LEFT	THRU	RIGHT	TOTAL	LEFT	THRU	RIGHT	TOTAL	LEFT	THRU	RIGHT	TOTAL	LEFT	THRU	RIGHT	TOTAL		
10:00 AM	4	13	15	32	7	10	4	21	9	11	15	35	4	12	3	19	107	415
10:15 AM	1	9	17	27	8	8	1	17	7	16	9	32	3	6	2	11	87	404
10:30 AM	5	21	13	39	11	14	5	30	8	16	18	42	3	7	2	12	123	419
10:45 AM	3	9	16	28	8	7	4	19	10	7	13	30	3	13	5	21	98	394
11:00 AM	0	14	14	28	5	13	3	21	6	10	13	29	3	13	2	18	96	408
11:15 AM	3	13	10	26	8	12	3	23	6	13	15	34	5	12	2	19	102	415
11:30 AM	1	11	10	22	10	17	1	28	11	16	13	40	1	6	1	8	98	431
11:45 AM	3	20	15	38	8	9	3	20	10	15	16	41	1	11	1	13	112	436
12:00 PM	3	12	11	26	7	13	3	23	11	9	16	36	0	14	4	18	103	419
12:15 PM	3	10	20	33	11	19	3	33	14	8	12	34	4	11	3	18	118	410
12:30 PM	1	14	7	22	12	17	5	34	12	8	15	35	0	9	3	12	103	405
12:45 PM	2	15	7	24	8	14	4	26	8	15	8	31	2	8	4	14	95	412
1:00 PM	1	6	8	15	10	13	4	27	12	9	15	36	2	12	2	16	94	435
1:15 PM	2	19	21	42	13	10	0	23	12	5	19	36	0	7	5	12	113	454
1:30 PM	3	19	10	32	11	13	2	26	15	11	16	42	1	4	5	10	110	476
1:45 PM	4	11	11	26	13	17	4	34	13	10	13	36	3	14	5	22	118	527
2:00 PM	0	22	9	31	13	18	1	32	12	8	19	39	1	5	5	11	113	630
2:15 PM	1	15	18	34	12	24	0	36	14	20	11	45	4	12	4	20	135	856
2:30 PM	2	11	17	30	14	43	3	60	32	7	17	56	2	8	5	15	161	917
2:45 PM	2	22	26	50	21	71	5	97	28	13	16	57	2	8	7	17	221	915
MD PEAK	15	152	129	296	72	167	14	253	115	62	133	310	9	33	16	58	917	917
PHF	0.63	0.42	0.62	0.50	0.86	0.59	0.70	0.65	0.78	0.67	0.54	0.65	0.75	0.92	0.57	0.85		

PCDS PAC

40th STREET and STANFORD DRIVE - TUESDAY - 8/29/2023



EXISTING 3:00 PM to 8:00 PM

BEGIN TIME	STANFORD DRIVE EASTBOUND				STANFORD DRIVE WESTBOUND				40th STREET NORTHBOUND				40th STREET SOUTHBOUND				ALL TOTAL	60 MIN. TOTAL
	LEFT	THRU	RIGHT	TOTAL	LEFT	THRU	RIGHT	TOTAL	LEFT	THRU	RIGHT	TOTAL	LEFT	THRU	RIGHT	TOTAL		
3:00 PM	6	90	52	148	20	37	2	59	37	19	62	118	2	9	3	14	339	895
3:15 PM	5	29	34	68	17	16	4	37	18	23	38	79	3	8	1	12	196	773
3:30 PM	2	25	22	49	15	18	4	37	23	13	26	62	1	7	3	11	159	768
3:45 PM	1	26	45	72	19	31	0	50	25	17	20	62	2	13	2	17	201	818
4:00 PM	2	29	35	66	24	23	1	48	39	23	28	90	3	8	2	13	217	815
4:15 PM	4	27	30	61	27	29	4	60	29	13	17	59	1	9	1	11	191	831
4:30 PM	1	15	20	36	26	28	7	61	37	8	45	90	4	14	4	22	209	862
4:45 PM	1	29	23	53	20	27	2	49	44	8	35	87	1	6	2	9	198	857
5:00 PM	4	23	26	53	24	33	3	60	40	10	44	94	3	19	4	26	233	830
5:15 PM	3	21	33	57	34	25	5	64	44	19	28	91	0	8	2	10	222	713
5:30 PM	8	17	21	46	17	38	3	58	45	13	30	88	2	8	2	12	204	603
5:45 PM	0	15	18	33	23	23	3	49	32	15	28	75	2	8	4	14	171	519
6:00 PM	0	13	13	26	11	16	5	32	18	9	14	41	3	11	3	17	116	432
6:15 PM	2	9	10	21	12	19	1	32	16	12	18	46	0	13	0	13	112	441
6:30 PM	3	17	9	29	12	12	1	25	23	16	14	53	5	7	1	13	120	406
6:45 PM	3	8	11	22	9	15	1	25	9	6	19	34	0	3	0	3	84	368
7:00 PM	2	8	11	21	11	12	2	25	20	11	33	64	4	10	1	15	125	329
7:15 PM	2	4	9	15	6	7	3	16	12	12	11	35	1	8	2	11	77	245
7:30 PM	2	9	14	25	4	2	1	7	17	10	15	42	1	6	1	8	82	200
7:45 PM	2	5	0	7	3	11	1	15	4	9	6	19	0	4	0	4	45	160
PM PEAK	14	170	153	337	71	102	10	183	103	72	146	321	8	37	9	54	895	895
PHF	0.58	0.47	0.74	0.57	0.89	0.69	0.63	0.78	0.70	0.78	0.59	0.78	0.67	0.71	0.75	0.79		

PCDS PAC

40th STREET and STANFORD DRIVE - TUESDAY - 8/29/2023



ADDITIONAL ANALYZED HOURS

BEGIN TIME	STANFORD DRIVE EASTBOUND				STANFORD DRIVE WESTBOUND				STANFORD DRIVE NORTHBOUND				STANFORD DRIVE SOUTHBOUND				60 MIN. TOTAL
	LEFT	THRU	RIGHT	TOTAL	LEFT	THRU	RIGHT	TOTAL	LEFT	THRU	RIGHT	TOTAL	LEFT	THRU	RIGHT	TOTAL	
4:30 to 5:30	9	88	102	199	104	113	17	234	165	45	152	362	8	47	12	67	862
PHF	0.56	0.76	0.77	0.87	0.76	0.86	0.61	0.91	0.94	0.59	0.84	0.96	0.50	0.62	0.75	0.64	
5:30 to 6:30	10	54	62	126	63	96	12	171	111	49	90	250	7	40	9	56	603
PHF	0.31	0.79	0.74	0.68	0.68	0.63	0.60	0.74	0.62	0.82	0.75	0.71	0.58	0.77	0.56	0.82	
7:00 to 8:00	8	26	34	68	24	32	7	63	53	42	65	160	6	28	4	38	329
PHF	1.00	0.72	0.61	0.68	0.55	0.67	0.58	0.63	0.66	0.88	0.49	0.63	0.38	0.70	0.50	0.63	

PCDS PAC

40th STREET and STANFORD DRIVE - TUESDAY - 8/29/2023

EXISTING TRAFFIC DISTRIBUTION

APPROACH	DAY		AM PEAK HOUR 7:15 AM to 8:15 AM		MD PEAK HOUR 2:30 PM to 3:30 PM		PM PEAK HOUR 3:00 PM to 4:00 PM		EARLY EVENING 5:30 PM to 6:30 PM		LATE EVENING 7:00 PM to 8:00 PM	
	VOLUME	PORTION	VOLUME	PORTION	VOLUME	PORTION	VOLUME	PORTION	VOLUME	PORTION	VOLUME	PORTION
40th STREET, NORTH OF STANFORD DRIVE	881	10%	96	9%	58	6%	54	6%	62	7%	38	12%
40th STREET, SOUTH OF STANFORD DRIVE	2,852	34%	239	22%	310	34%	321	36%	348	42%	160	49%
STANFORD DRIVE, EAST OF 40th STREET	2,313	27%	415	38%	253	28%	183	20%	231	28%	63	19%
STANFORD DRIVE, WEST OF 40th STREET	2,443	29%	353	31%	296	32%	337	38%	189	23%	68	20%
TOTAL	8,489	100%	1,103	100%	917	100%	895	100%	830	100%	329	100%

DEPARTURE	DAY		AM PEAK HOUR 7:15 AM to 8:15 AM		MD PEAK HOUR 2:30 PM to 3:30 PM		PM PEAK HOUR 3:00 PM to 4:00 PM		EARLY EVENING 5:30 PM to 6:30 PM		LATE EVENING 7:00 PM to 8:00 PM	
	VOLUME	PORTION	VOLUME	PORTION	VOLUME	PORTION	VOLUME	PORTION	VOLUME	PORTION	VOLUME	PORTION
40th STREET, NORTH OF STANFORD DRIVE	996	12%	61	6%	91	10%	96	11%	86	10%	57	17%
40th STREET, SOUTH OF STANFORD DRIVE	2,712	32%	441	40%	234	26%	261	29%	239	29%	86	26%
STANFORD DRIVE, EAST OF 40th STREET	2,343	28%	274	25%	294	32%	324	36%	213	26%	97	29%
STANFORD DRIVE, WEST OF 40th STREET	2,438	29%	327	29%	298	32%	214	24%	292	35%	89	28%
TOTAL	8,489	100%	1,103	100%	917	100%	895	100%	830	100%	329	100%

Analysis By: PEB Date: 9/6/2023



Appendix C

Level of Service



Appendix C.1

Level of Service

Summary



40th and STANFORD: 7:15 to 8:15 AM PEAK HOUR

	EXISTING 2023		ADJUSTED 2023		2025	
	DELAY	LOS	DELAY	LOS	DELAY	LOS
Intersection	40.4	E	46.4	E	64.2	F
Northbound	10.4	B	10.7	B	11.5	B
Southbound	17.6	C	18.8	C	23.5	C
Eastbound	37.9	E	43.5	E	61.2	F
Westbound	59.2	F	68.9	F	97.2	F

40th and STANFORD: 2:30 to 3:30 PM PEAK HOUR

	EXISTING 2023		ADJUSTED 2023		2025	
	DELAY	LOS	DELAY	LOS	DELAY	LOS
Intersection	14.7	B	15.6	C	18.4	C
Northbound	20.5	C	22.3	C	27.7	D
Southbound	8.2	A	8.4	A	9.1	A
Eastbound	14.5	B	15.2	C	17.5	C
Westbound	10.1	B	10.4	B	11.9	B

40th and STANFORD: 4:30 to 5:30 PM PEAK HOUR

	EXISTING 2023		ADJUSTED 2023		2025	
	DELAY	LOS	DELAY	LOS	DELAY	LOS
Intersection	8.3	A	8.5	A	9.1	A
Northbound	9.2	A	9.4	A	10.2	B
Southbound	6.8	A	6.9	A	7.4	A
Eastbound	7.4	A	7.5	A	8.2	A
Westbound	8.4	A	8.6	A	9.1	A

40th and STANFORD: 5:30 to 6:30 PM PEAK HOUR

	EXISTING 2023		ADJUSTED 2023		2025		2025 WITH PAC	
	DELAY	LOS	DELAY	LOS	DELAY	LOS	DELAY	LOS
Intersection	5.5	A	5.6	A	5.9	A	6.5	A
Northbound	5.7	A	5.8	A	6.1	A	6.1	A
Southbound	5.1	A	5.2	A	5.5	A	6.6	A
Eastbound	4.6	A	4.7	A	4.9	A	5.2	A
Westbound	6.1	A	6.2	A	6.5	A	7.5	A

40th and STANFORD: 7:00 to 8:00 PM PEAK HOUR

	EXISTING 2023		ADJUSTED 2023		2025		2025 WITH PAC	
	DELAY	LOS	DELAY	LOS	DELAY	LOS	DELAY	LOS
Intersection	4.1	A	4.2	A	4.4	A	5.2	A
Northbound	4.6	A	4.7	A	4.9	A	6.3	A
Southbound	3.6	A	3.7	A	4.1	A	4.1	A
Eastbound	3.6	A	3.6	A	4.9	A	4.8	A
Westbound	3.8	A	3.8	A	4.1	A	4.2	A

Appendix C.2
Level of Service
2023 Existing and Adjusted



Existing 2023 - 7:15 to 8:15 AM PEAK

1: 40th Street & Stanford Road

Intersection				
Intersection Delay, s/veh	40.4			
Intersection LOS	E			
Approach	EB	WB	NB	SB
Entry Lanes	1	1	1	1
Conflicting Circle Lanes	1	1	1	1
Adj Approach Flow, veh/h	566	868	379	157
Demand Flow Rate, veh/h	577	885	387	160
Vehicles Circulating, veh/h	548	268	297	1056
Vehicles Exiting, veh/h	668	416	828	97
Follow-Up Headway, s	3.186	3.186	3.186	3.186
Ped Vol Crossing Leg, #/h	0	0	0	0
Ped Cap Adj	1.000	1.000	1.000	1.000
Approach Delay, s/veh	37.9	59.2	10.4	17.6
Approach LOS	E	F	B	C
Lane	Left	Left	Left	Left
Designated Moves	LTR	LTR	LTR	LTR
Assumed Moves	LTR	LTR	LTR	LTR
RT Channelized				
Lane Util	1.000	1.000	1.000	1.000
Critical Headway, s	5.193	5.193	5.193	5.193
Entry Flow, veh/h	577	885	387	160
Cap Entry Lane, veh/h	653	864	840	393
Entry HV Adj Factor	0.980	0.980	0.979	0.982
Flow Entry, veh/h	566	868	379	157
Cap Entry, veh/h	640	847	822	386
V/C Ratio	0.883	1.024	0.461	0.407
Control Delay, s/veh	37.9	59.2	10.4	17.6
LOS	E	F	B	C
95th %tile Queue, veh	11	19	2	2

Existing 2023 - 2:30 to 3:30 PM PEAK

1: 40th Street & Stanford Road

Intersection				
Intersection Delay, s/veh	14.7			
Intersection LOS	B			
Approach	EB	WB	NB	SB
Entry Lanes	1	1	1	1
Conflicting Circle Lanes	1	1	1	1
Adj Approach Flow, veh/h	594	387	486	146
Demand Flow Rate, veh/h	605	395	496	150
Vehicles Circulating, veh/h	202	269	479	525
Vehicles Exiting, veh/h	473	706	328	139
Follow-Up Headway, s	3.186	3.186	3.186	3.186
Ped Vol Crossing Leg, #/h	0	0	0	0
Ped Cap Adj	1.000	1.000	1.000	1.000
Approach Delay, s/veh	14.5	10.1	20.5	8.2
Approach LOS	B	B	C	A
Lane	Left	Left	Left	Left
Designated Moves	LTR	LTR	LTR	LTR
Assumed Moves	LTR	LTR	LTR	LTR
RT Channelized				
Lane Util	1.000	1.000	1.000	1.000
Critical Headway, s	5.193	5.193	5.193	5.193
Entry Flow, veh/h	605	395	496	150
Cap Entry Lane, veh/h	923	863	700	668
Entry HV Adj Factor	0.981	0.981	0.980	0.976
Flow Entry, veh/h	594	387	486	146
Cap Entry, veh/h	906	847	686	652
V/C Ratio	0.655	0.457	0.709	0.224
Control Delay, s/veh	14.5	10.1	20.5	8.2
LOS	B	B	C	A
95th %tile Queue, veh	5	2	6	1

Existing 2023 - 4:30 to 5:30 PM PEAK

1: 40th Street & Stanford Road

Intersection				
Intersection Delay, s/veh	8.3			
Intersection LOS	A			
Approach	EB	WB	NB	SB
Entry Lanes	1	1	1	1
Conflicting Circle Lanes	1	1	1	1
Adj Approach Flow, veh/h	264	296	433	108
Demand Flow Rate, veh/h	269	303	443	110
Vehicles Circulating, veh/h	234	274	150	454
Vehicles Exiting, veh/h	330	319	353	123
Follow-Up Headway, s	3.186	3.186	3.186	3.186
Ped Vol Crossing Leg, #/h	0	0	0	0
Ped Cap Adj	1.000	1.000	1.000	1.000
Approach Delay, s/veh	7.4	8.4	9.2	6.8
Approach LOS	A	A	A	A
Lane	Left	Left	Left	Left
Designated Moves	LTR	LTR	LTR	LTR
Assumed Moves	LTR	LTR	LTR	LTR
RT Channelized				
Lane Util	1.000	1.000	1.000	1.000
Critical Headway, s	5.193	5.193	5.193	5.193
Entry Flow, veh/h	269	303	443	110
Cap Entry Lane, veh/h	894	859	973	718
Entry HV Adj Factor	0.980	0.978	0.978	0.986
Flow Entry, veh/h	264	296	433	108
Cap Entry, veh/h	877	840	952	708
V/C Ratio	0.301	0.353	0.456	0.153
Control Delay, s/veh	7.4	8.4	9.2	6.8
LOS	A	A	A	A
95th %tile Queue, veh	1	2	2	1

Intersection				
Intersection Delay, s/veh	5.5			
Intersection LOS	A			
Approach	EB	WB	NB	SB
Entry Lanes	1	1	1	1
Conflicting Circle Lanes	1	1	1	1
Adj Approach Flow, veh/h	184	265	359	91
Demand Flow Rate, veh/h	188	270	366	92
Vehicles Circulating, veh/h	176	277	111	433
Vehicles Exiting, veh/h	349	200	253	114
Ped Vol Crossing Leg, #/h	0	0	0	0
Ped Cap Adj	1.000	1.000	1.000	1.000
Approach Delay, s/veh	4.6	6.1	5.7	5.1
Approach LOS	A	A	A	A
Lane	Left	Left	Left	Left
Designated Moves	LTR	LTR	LTR	LTR
Assumed Moves	LTR	LTR	LTR	LTR
RT Channelized				
Lane Util	1.000	1.000	1.000	1.000
Follow-Up Headway, s	2.609	2.609	2.609	2.609
Critical Headway, s	4.976	4.976	4.976	4.976
Entry Flow, veh/h	188	270	366	92
Cap Entry Lane, veh/h	1153	1040	1232	887
Entry HV Adj Factor	0.977	0.981	0.980	0.985
Flow Entry, veh/h	184	265	359	91
Cap Entry, veh/h	1126	1021	1208	874
V/C Ratio	0.163	0.260	0.297	0.104
Control Delay, s/veh	4.6	6.1	5.7	5.1
LOS	A	A	A	A
95th %tile Queue, veh	1	1	1	0

Existing - 7:00 to 8:00 PM

1: 40th Street & Stanford Road

Intersection				
Intersection Delay, s/veh	4.1			
Intersection LOS	A			
Approach	EB	WB	NB	SB
Entry Lanes	1	1	1	1
Conflicting Circle Lanes	1	1	1	1
Adj Approach Flow, veh/h	100	104	261	64
Demand Flow Rate, veh/h	102	106	267	65
Vehicles Circulating, veh/h	102	139	61	176
Vehicles Exiting, veh/h	139	189	143	69
Ped Vol Crossing Leg, #/h	0	0	0	0
Ped Cap Adj	1.000	1.000	1.000	1.000
Approach Delay, s/veh	3.6	3.8	4.6	3.6
Approach LOS	A	A	A	A
Lane	Left	Left	Left	Left
Designated Moves	LTR	LTR	LTR	LTR
Assumed Moves	LTR	LTR	LTR	LTR
RT Channelized				
Lane Util	1.000	1.000	1.000	1.000
Follow-Up Headway, s	2.609	2.609	2.609	2.609
Critical Headway, s	4.976	4.976	4.976	4.976
Entry Flow, veh/h	102	106	267	65
Cap Entry Lane, veh/h	1244	1197	1297	1153
Entry HV Adj Factor	0.983	0.982	0.978	0.988
Flow Entry, veh/h	100	104	261	64
Cap Entry, veh/h	1222	1175	1268	1139
V/C Ratio	0.082	0.089	0.206	0.056
Control Delay, s/veh	3.6	3.8	4.6	3.6
LOS	A	A	A	A
95th %tile Queue, veh	0	0	1	0

Adjusted 2023 - 7:15 to 8:15 AM PEAK

1: 40th Street & Stanford Road

Intersection				
Intersection Delay, s/veh	46.4			
Intersection LOS	E			
Approach	EB	WB	NB	SB
Entry Lanes	1	1	1	1
Conflicting Circle Lanes	1	1	1	1
Adj Approach Flow, veh/h	580	889	389	162
Demand Flow Rate, veh/h	591	907	397	165
Vehicles Circulating, veh/h	561	275	303	1083
Vehicles Exiting, veh/h	687	425	849	99
Follow-Up Headway, s	3.186	3.186	3.186	3.186
Ped Vol Crossing Leg, #/h	0	0	0	0
Ped Cap Adj	1.000	1.000	1.000	1.000
Approach Delay, s/veh	43.5	68.9	10.7	18.8
Approach LOS	E	F	B	C
Lane	Left	Left	Left	Left
Designated Moves	LTR	LTR	LTR	LTR
Assumed Moves	LTR	LTR	LTR	LTR
RT Channelized				
Lane Util	1.000	1.000	1.000	1.000
Critical Headway, s	5.193	5.193	5.193	5.193
Entry Flow, veh/h	591	907	397	165
Cap Entry Lane, veh/h	645	858	835	383
Entry HV Adj Factor	0.981	0.981	0.979	0.982
Flow Entry, veh/h	580	889	389	162
Cap Entry, veh/h	632	842	817	376
V/C Ratio	0.917	1.057	0.476	0.431
Control Delay, s/veh	43.5	68.9	10.7	18.8
LOS	E	F	B	C
95th %tile Queue, veh	12	21	3	2

Intersection				
Intersection Delay, s/veh	15.6			
Intersection LOS	C			
Approach	EB	WB	NB	SB
Entry Lanes	1	1	1	1
Conflicting Circle Lanes	1	1	1	1
Adj Approach Flow, veh/h	608	396	499	150
Demand Flow Rate, veh/h	619	404	509	154
Vehicles Circulating, veh/h	208	276	491	538
Vehicles Exiting, veh/h	484	724	336	142
Follow-Up Headway, s	3.186	3.186	3.186	3.186
Ped Vol Crossing Leg, #/h	0	0	0	0
Ped Cap Adj	1.000	1.000	1.000	1.000
Approach Delay, s/veh	15.2	10.4	22.3	8.4
Approach LOS	C	B	C	A
Lane	Left	Left	Left	Left
Designated Moves	LTR	LTR	LTR	LTR
Assumed Moves	LTR	LTR	LTR	LTR
RT Channelized				
Lane Util	1.000	1.000	1.000	1.000
Critical Headway, s	5.193	5.193	5.193	5.193
Entry Flow, veh/h	619	404	509	154
Cap Entry Lane, veh/h	918	857	692	660
Entry HV Adj Factor	0.982	0.981	0.981	0.977
Flow Entry, veh/h	608	396	499	150
Cap Entry, veh/h	901	841	678	644
V/C Ratio	0.674	0.471	0.736	0.233
Control Delay, s/veh	15.2	10.4	22.3	8.4
LOS	C	B	C	A
95th %tile Queue, veh	5	3	6	1

Intersection				
Intersection Delay, s/veh	8.5			
Intersection LOS	A			
Approach	EB	WB	NB	SB
Entry Lanes	1	1	1	1
Conflicting Circle Lanes	1	1	1	1
Adj Approach Flow, veh/h	270	304	444	109
Demand Flow Rate, veh/h	275	311	454	111
Vehicles Circulating, veh/h	239	280	152	466
Vehicles Exiting, veh/h	338	326	362	125
Follow-Up Headway, s	3.186	3.186	3.186	3.186
Ped Vol Crossing Leg, #/h	0	0	0	0
Ped Cap Adj	1.000	1.000	1.000	1.000
Approach Delay, s/veh	7.5	8.6	9.4	6.9
Approach LOS	A	A	A	A
Lane	Left	Left	Left	Left
Designated Moves	LTR	LTR	LTR	LTR
Assumed Moves	LTR	LTR	LTR	LTR
RT Channelized				
Lane Util	1.000	1.000	1.000	1.000
Critical Headway, s	5.193	5.193	5.193	5.193
Entry Flow, veh/h	275	311	454	111
Cap Entry Lane, veh/h	890	854	971	709
Entry HV Adj Factor	0.981	0.978	0.979	0.986
Flow Entry, veh/h	270	304	444	109
Cap Entry, veh/h	872	836	950	699
V/C Ratio	0.309	0.364	0.468	0.157
Control Delay, s/veh	7.5	8.6	9.4	6.9
LOS	A	A	A	A
95th %tile Queue, veh	1	2	3	1

Intersection				
Intersection Delay, s/veh	5.6			
Intersection LOS	A			
Approach	EB	WB	NB	SB
Entry Lanes	1	1	1	1
Conflicting Circle Lanes	1	1	1	1
Adj Approach Flow, veh/h	188	272	368	93
Demand Flow Rate, veh/h	192	277	375	94
Vehicles Circulating, veh/h	181	283	113	445
Vehicles Exiting, veh/h	358	205	260	115
Ped Vol Crossing Leg, #/h	0	0	0	0
Ped Cap Adj	1.000	1.000	1.000	1.000
Approach Delay, s/veh	4.7	6.2	5.8	5.2
Approach LOS	A	A	A	A
Lane	Left	Left	Left	Left
Designated Moves	LTR	LTR	LTR	LTR
Assumed Moves	LTR	LTR	LTR	LTR
RT Channelized				
Lane Util	1.000	1.000	1.000	1.000
Follow-Up Headway, s	2.609	2.609	2.609	2.609
Critical Headway, s	4.976	4.976	4.976	4.976
Entry Flow, veh/h	192	277	375	94
Cap Entry Lane, veh/h	1147	1034	1230	876
Entry HV Adj Factor	0.977	0.982	0.981	0.985
Flow Entry, veh/h	188	272	368	93
Cap Entry, veh/h	1121	1015	1206	863
V/C Ratio	0.167	0.268	0.305	0.107
Control Delay, s/veh	4.7	6.2	5.8	5.2
LOS	A	A	A	A
95th %tile Queue, veh	1	1	1	0

Intersection				
Intersection Delay, s/veh	4.2			
Intersection LOS	A			
Approach	EB	WB	NB	SB
Entry Lanes	1	1	1	1
Conflicting Circle Lanes	1	1	1	1
Adj Approach Flow, veh/h	103	106	268	65
Demand Flow Rate, veh/h	105	108	274	66
Vehicles Circulating, veh/h	104	142	63	180
Vehicles Exiting, veh/h	142	195	146	70
Ped Vol Crossing Leg, #/h	0	0	0	0
Ped Cap Adj	1.000	1.000	1.000	1.000
Approach Delay, s/veh	3.6	3.8	4.7	3.7
Approach LOS	A	A	A	A
Lane	Left	Left	Left	Left
Designated Moves	LTR	LTR	LTR	LTR
Assumed Moves	LTR	LTR	LTR	LTR
RT Channelized				
Lane Util	1.000	1.000	1.000	1.000
Follow-Up Headway, s	2.609	2.609	2.609	2.609
Critical Headway, s	4.976	4.976	4.976	4.976
Entry Flow, veh/h	105	108	274	66
Cap Entry Lane, veh/h	1241	1194	1294	1148
Entry HV Adj Factor	0.983	0.982	0.978	0.988
Flow Entry, veh/h	103	106	268	65
Cap Entry, veh/h	1220	1172	1266	1134
V/C Ratio	0.085	0.090	0.212	0.057
Control Delay, s/veh	3.6	3.8	4.7	3.7
LOS	A	A	A	A
95th %tile Queue, veh	0	0	1	0

Appendix C.3

Level-of-Service

2025 Ambient and 2025 with Performing Arts Center



Intersection				
Intersection Delay, s/veh	64.2			
Intersection LOS	F			
Approach	EB	WB	NB	SB
Entry Lanes	1	1	1	1
Conflicting Circle Lanes	1	1	1	1
Adj Approach Flow, veh/h	609	941	411	186
Demand Flow Rate, veh/h	621	959	419	189
Vehicles Circulating, veh/h	594	294	316	1143
Vehicles Exiting, veh/h	738	441	899	110
Follow-Up Headway, s	3.186	3.186	3.186	3.186
Ped Vol Crossing Leg, #/h	0	0	0	0
Ped Cap Adj	1.000	1.000	1.000	1.000
Approach Delay, s/veh	61.2	97.2	11.5	23.5
Approach LOS	F	F	B	C
Lane	Left	Left	Left	Left
Designated Moves	LTR	LTR	LTR	LTR
Assumed Moves	LTR	LTR	LTR	LTR
RT Channelized				
Lane Util	1.000	1.000	1.000	1.000
Critical Headway, s	5.193	5.193	5.193	5.193
Entry Flow, veh/h	621	959	419	189
Cap Entry Lane, veh/h	624	842	824	360
Entry HV Adj Factor	0.981	0.981	0.980	0.984
Flow Entry, veh/h	609	941	411	186
Cap Entry, veh/h	612	826	807	354
V/C Ratio	0.995	1.139	0.509	0.525
Control Delay, s/veh	61.2	97.2	11.5	23.5
LOS	F	F	B	C
95th %tile Queue, veh	15	27	3	3

Intersection				
Intersection Delay, s/veh	18.4			
Intersection LOS	C			
Approach	EB	WB	NB	SB
Entry Lanes	1	1	1	1
Conflicting Circle Lanes	1	1	1	1
Adj Approach Flow, veh/h	639	427	530	161
Demand Flow Rate, veh/h	653	436	540	165
Vehicles Circulating, veh/h	224	309	517	576
Vehicles Exiting, veh/h	517	748	360	169
Follow-Up Headway, s	3.186	3.186	3.186	3.186
Ped Vol Crossing Leg, #/h	0	0	0	0
Ped Cap Adj	1.000	1.000	1.000	1.000
Approach Delay, s/veh	17.5	11.9	27.7	9.1
Approach LOS	C	B	D	A
Lane	Left	Left	Left	Left
Designated Moves	LTR	LTR	LTR	LTR
Assumed Moves	LTR	LTR	LTR	LTR
RT Channelized				
Lane Util	1.000	1.000	1.000	1.000
Critical Headway, s	5.193	5.193	5.193	5.193
Entry Flow, veh/h	653	436	540	165
Cap Entry Lane, veh/h	903	830	674	635
Entry HV Adj Factor	0.979	0.979	0.981	0.978
Flow Entry, veh/h	639	427	530	161
Cap Entry, veh/h	884	812	661	621
V/C Ratio	0.723	0.526	0.801	0.260
Control Delay, s/veh	17.5	11.9	27.7	9.1
LOS	C	B	D	A
95th %tile Queue, veh	6	3	8	1

Intersection				
Intersection Delay, s/veh	9.1			
Intersection LOS	A			
Approach	EB	WB	NB	SB
Entry Lanes	1	1	1	1
Conflicting Circle Lanes	1	1	1	1
Adj Approach Flow, veh/h	293	318	466	130
Demand Flow Rate, veh/h	299	325	476	132
Vehicles Circulating, veh/h	267	300	173	486
Vehicles Exiting, veh/h	351	349	393	139
Follow-Up Headway, s	3.186	3.186	3.186	3.186
Ped Vol Crossing Leg, #/h	0	0	0	0
Ped Cap Adj	1.000	1.000	1.000	1.000
Approach Delay, s/veh	8.2	9.1	10.2	7.4
Approach LOS	A	A	B	A
Lane	Left	Left	Left	Left
Designated Moves	LTR	LTR	LTR	LTR
Assumed Moves	LTR	LTR	LTR	LTR
RT Channelized				
Lane Util	1.000	1.000	1.000	1.000
Critical Headway, s	5.193	5.193	5.193	5.193
Entry Flow, veh/h	299	325	476	132
Cap Entry Lane, veh/h	865	837	950	695
Entry HV Adj Factor	0.981	0.979	0.980	0.985
Flow Entry, veh/h	293	318	466	130
Cap Entry, veh/h	849	820	931	685
V/C Ratio	0.346	0.388	0.501	0.190
Control Delay, s/veh	8.2	9.1	10.2	7.4
LOS	A	A	B	A
95th %tile Queue, veh	2	2	3	1

Intersection				
Intersection Delay, s/veh	5.9			
Intersection LOS	A			
Approach	EB	WB	NB	SB
Entry Lanes	1	1	1	1
Conflicting Circle Lanes	1	1	1	1
Adj Approach Flow, veh/h	203	295	388	96
Demand Flow Rate, veh/h	208	300	396	97
Vehicles Circulating, veh/h	190	293	124	481
Vehicles Exiting, veh/h	388	227	274	112
Ped Vol Crossing Leg, #/h	0	0	0	0
Ped Cap Adj	1.000	1.000	1.000	1.000
Approach Delay, s/veh	4.9	6.5	6.1	5.5
Approach LOS	A	A	A	A
Lane	Left	Left	Left	Left
Designated Moves	LTR	LTR	LTR	LTR
Assumed Moves	LTR	LTR	LTR	LTR
RT Channelized				
Lane Util	1.000	1.000	1.000	1.000
Follow-Up Headway, s	2.609	2.609	2.609	2.609
Critical Headway, s	4.976	4.976	4.976	4.976
Entry Flow, veh/h	208	300	396	97
Cap Entry Lane, veh/h	1137	1023	1216	845
Entry HV Adj Factor	0.978	0.982	0.979	0.985
Flow Entry, veh/h	203	295	388	96
Cap Entry, veh/h	1112	1005	1191	833
V/C Ratio	0.183	0.293	0.326	0.115
Control Delay, s/veh	4.9	6.5	6.1	5.5
LOS	A	A	A	A
95th %tile Queue, veh	1	1	1	0

Intersection				
Intersection Delay, s/veh	4.4			
Intersection LOS	A			
Approach	EB	WB	NB	SB
Entry Lanes	1	1	1	1
Conflicting Circle Lanes	1	1	1	1
Adj Approach Flow, veh/h	118	132	291	103
Demand Flow Rate, veh/h	120	134	297	105
Vehicles Circulating, veh/h	141	161	80	210
Vehicles Exiting, veh/h	174	216	181	85
Ped Vol Crossing Leg, #/h	0	0	0	0
Ped Cap Adj	1.000	1.000	1.000	1.000
Approach Delay, s/veh	3.9	4.1	4.9	4.1
Approach LOS	A	A	A	A
Lane	Left	Left	Left	Left
Designated Moves	LTR	LTR	LTR	LTR
Assumed Moves	LTR	LTR	LTR	LTR
RT Channelized				
Lane Util	1.000	1.000	1.000	1.000
Follow-Up Headway, s	2.609	2.609	2.609	2.609
Critical Headway, s	4.976	4.976	4.976	4.976
Entry Flow, veh/h	120	134	297	105
Cap Entry Lane, veh/h	1195	1171	1272	1114
Entry HV Adj Factor	0.985	0.984	0.979	0.980
Flow Entry, veh/h	118	132	291	103
Cap Entry, veh/h	1177	1152	1245	1091
V/C Ratio	0.100	0.114	0.234	0.094
Control Delay, s/veh	3.9	4.1	4.9	4.1
LOS	A	A	A	A
95th %tile Queue, veh	0	0	1	0

Intersection				
Intersection Delay, s/veh	6.5			
Intersection LOS	A			
Approach	EB	WB	NB	SB
Entry Lanes	1	1	1	1
Conflicting Circle Lanes	1	1	1	1
Adj Approach Flow, veh/h	203	372	388	138
Demand Flow Rate, veh/h	208	379	396	140
Vehicles Circulating, veh/h	246	293	124	560
Vehicles Exiting, veh/h	454	227	330	112
Ped Vol Crossing Leg, #/h	0	0	0	0
Ped Cap Adj	1.000	1.000	1.000	1.000
Approach Delay, s/veh	5.2	7.5	6.1	6.6
Approach LOS	A	A	A	A
Lane	Left	Left	Left	Left
Designated Moves	LTR	LTR	LTR	LTR
Assumed Moves	LTR	LTR	LTR	LTR
RT Channelized				
Lane Util	1.000	1.000	1.000	1.000
Follow-Up Headway, s	2.609	2.609	2.609	2.609
Critical Headway, s	4.976	4.976	4.976	4.976
Entry Flow, veh/h	208	379	396	140
Cap Entry Lane, veh/h	1074	1023	1216	779
Entry HV Adj Factor	0.978	0.982	0.979	0.985
Flow Entry, veh/h	203	372	388	138
Cap Entry, veh/h	1050	1005	1191	768
V/C Ratio	0.194	0.370	0.326	0.180
Control Delay, s/veh	5.2	7.5	6.1	6.6
LOS	A	A	A	A
95th %tile Queue, veh	1	2	1	1

Intersection				
Intersection Delay, s/veh	5.2			
Intersection LOS	A			
Approach	EB	WB	NB	SB
Entry Lanes	1	1	1	1
Conflicting Circle Lanes	1	1	1	1
Adj Approach Flow, veh/h	228	132	348	103
Demand Flow Rate, veh/h	232	134	355	105
Vehicles Circulating, veh/h	141	183	192	210
Vehicles Exiting, veh/h	174	364	181	107
Ped Vol Crossing Leg, #/h	0	0	0	0
Ped Cap Adj	1.000	1.000	1.000	1.000
Approach Delay, s/veh	4.8	4.2	6.3	4.1
Approach LOS	A	A	A	A
Lane	Left	Left	Left	Left
Designated Moves	LTR	LTR	LTR	LTR
Assumed Moves	LTR	LTR	LTR	LTR
RT Channelized				
Lane Util	1.000	1.000	1.000	1.000
Follow-Up Headway, s	2.609	2.609	2.609	2.609
Critical Headway, s	4.976	4.976	4.976	4.976
Entry Flow, veh/h	232	134	355	105
Cap Entry Lane, veh/h	1195	1145	1134	1114
Entry HV Adj Factor	0.983	0.984	0.979	0.980
Flow Entry, veh/h	228	132	348	103
Cap Entry, veh/h	1175	1126	1111	1091
V/C Ratio	0.194	0.117	0.313	0.094
Control Delay, s/veh	4.8	4.2	6.3	4.1
LOS	A	A	A	A
95th %tile Queue, veh	1	0	1	0